

ESTIMATED QUANTITIES

SITE PREPARATION (TOP SOIL):

MOBILIZATION:

DUCKS UNLIMITED

ALPINE WETLANDS WY - 178 - 1

LOCATED IN PARTS OF SECTIONS 3, 4, & 10 TOWNSHIP 36N, RANGE 119W, 6TH P.M., LINCOLN COUNTY, WYOMING

DEWATERING: 1 L.S. **EXCAVATION:** GRADE IN SETTLING BASIN 520 C,Y.-P CLEANOUT & REGRADE COOT DITCH 710 C.Y.-P CONSTRUCTED TOPOGRAPHY: RE-GRADE HEADGATE AREA REINFORCE HEADGATE AREA 1,383 C.Y.-P 230 C.Y.-P WATER CONTROL STRUCTURES (WCS) - SUPPLY & INSTALL: 48" FRESNO SERIES 6600 MODEL 101C SCREW GATE (12' TALL) 1 EA. 36" FRESNO SERIES 6600 MODEL 101C SCREW GATE (12' TALL) 1 EA. 24"ø (5' TALL) INLINE WCS CULVERTS & PIPE - SUPPLY & INSTALL: ALBC ALUMINUM BOX CULVERT 1 EA. (16'-10" SPAN x 8'-3" RISE x 45'-3" LENGTH) 48" REINFORCED CONCRETE PIPE 25 L.F.-A 36"ø REINFORCED CONCRETE PIPE 35 L.F.-A 24"ø PVC PIPE (SDR 51)

1 L.S.

1 L.S.

52 L.F.-A CAST-IN-PLACE REINFORCED CONCRETE:
REINFORCED CONCRETE FLUSHING CULVERT HEADWALL 1 EA. REINFORCED CONCRETE HEADWALL/TAILWALL 1 EA. REINFORCED CONCRETE TAILWALL 1 EA. ROCK, RIPRAP, & REVETMENT - SUPPLY & PLACE:
DU CLASS IV ROCK RIPRAP W/ FILTER FABRIC
DU CLASS II ROCK RIPRAP W/ FILTER FABRIC 40 C.Y.-P

135 C.Y.-P ROCK PITRUN 25 C.Y.-P WELL-GRADED SAND 11.5 C.Y.-P 1" MINUS ANGULAR GRANULAR AGGREGATE 12 C.Y.-P MISCELLANEOUS MAINTENANCE/DISPOSAL:
REMOVAL & OFFSITE DISPOSAL OF EXISTING 1 L.S.

PIPE & WATER CONTROL STRUCTURES

TRAFFIC MAINTENANCE AND CONTROL INSTALL & MAINTAIN TRAFFIC CONTROL SIGNALS, 1 L.S. SIGNAGE & EQUIPMENT


C.Y.-P - PAYMENT WILL BE BASED ON THE PLAN QUANTITY LISTED ABOVE. L.F.-A - PAYMENT WILL BE BASED ON ACTUAL QUANTITY EXCAVATED, FILLED, RE-GRADED, CLEANED OUT, OR SUPPLIED AND INSTALLED

SPECIFICATIONS

<u>ole</u>	CIFICATIONS
101	GENERAL CONDITIONS
102	SUPPLEMENTAL CONDITIONS
201	MOBILIZATION
202	SITE PREPARATION
203	EXCAVATION
206	CONSTRUCTED TOPOGRAPHY
301	WATER CONTROL STRUCTURES
303	CULVERT AND PIPE INSTALLATION
304	CAST-IN-PLACE REINFORCED CONCRETE
305	RIPRAP, REVETMENT & AGGREGATE PLACEMENT
307	SHEET PILING
311	REMOVAL OF EXISTING CULVERTS AND STRUCTURE
401	SOIL EROSION AND POLLUTION CONTROL

TRAFFIC MAINTENANCE AND CONTROL

RIVER



PLAN INDEX

- TITLE PAGE & LOCATION MAP
- OVERALL PLAN
- FLUSHING CULVERT HEADWALL FLUSHING CULVERT SCREW GATE
- MAIN HEADWALL
- MAIN SCREW GATE
- MAIN TAILWALL
- REGRADE HEADGATE AREA, MOVE EX. ROCK PENINSULA
- & GRADE-IN SETTLING BASIN CLEANOUT & REGRADE COOT DITCH
- TEMPORARY ROAD CONSTRUCTION
- ROAD CULVERT REPLACEMENT
- 11A CONTECH CULVERT DESIGN SHEETS 1-2
- 11B CONTECH CULVERT DESIGN SHEETS 3-4 11C CONTECH CULVERT DESIGN SHEETS 5-6

- 11D CONTECH CULVERT DESIGN SHEETS 7-8
- 11E CONTECH CULVERT DESIGN SHEETS 9-10
- 12 RUDDY DUCK RESERVOIR ARMORED SPILLWAY
- PINTAIL RESERVOIR ARMORED SPILLWAY & ROCK CHECK
- TEAL RESERVOIR ARMORED SPILLWAY
- MERGANSER RESERVOIR ARMORED SPILLWAY
- GOLDENEYE RESERVOIR ARMORED SPILLWAY
- GOLDENEYE WCS REPLACEMENT
- TRAFFIC CONTROL PLAN
- STORMWATER POLLUTION PREVENTION PLAN 19
- SWPPP NOTES



BEFORE THE START OF CONSTRUCTION. THE OWNER OF ANY UTILITIES INVOLVED MUST BE NOTIFIED. THE EXCAVATOR/CONTRACTOR IS RESPONSIBLE FOR GIVING THIS NOTICE BY CALLING "ONE CALL OF WYOMING" AT 811.

A 72 HOUR NOTIFICATION AND FULL DESCRIPTION OF LOCATION IS REQUIRED.

DU PROJECT ENGINEER: THOMAS PARKER, P.E. (970) 692-3375





WETLANDS ALPINE


DATE: 04/16/2025


SHEET TITLE:
TITLE PAGE & LOCATION MAP

SCALES ARE ACCURATE ON 24"X36" SHEET SIZE II PROJECT NUMBER

> WY-178-1 SHEET NUMBER:

SHEET 1 OF 20





THIS MATERIAL, DATA AND INFORMATION IS THE PROPERTY OF DUCKS UNLIMITED, INC. IT MAY NOT BE USED OR REPRODUCED FOR ANY PURPOSE WITHOUT THE PRIOR WRITTEN CONSENT OF AN AUTHORIZED AGENT OF DUCKS UNLIMITED, INC. DUCKS UNLIMITED, INC. MAKES NO REPRESENTATION OR WARRANTY OF ANY KIND REGARDING THIS MATERIAL, DATA AND INFORMATION, INCLUDING, BUT NOT LIMITED TO, THE ACCURACY OF THE MATERIAL, DATA AND INFORMATION OR ITS SUITABILITY PURPOSE. ALL USE OF THE MATERIAL, DATA AND INFORMATION, USER AGREES THAT DUCKS UNLIMITED, INC. IS NOT RESPONSIBLE FOR THEIR USE OF THE MATERIAL, DATA AND INFORMATION OR THE RESULTS THEREOF.

INVOLVED MUST BE NOTIFIED. THE EXCAVATOR/CONTRACTOR IS RESPONSIBLE FOR GIVING THIS NOTICE BY CALLING "ONE CALL OF WYOMING" AT 811.

A 72 HOUR NOTIFICATION AND FULL DESCRIPTION OF LOCATION IS REQUIRED.

LEGEND

PROPERTY BOUNDARY

FULL SERVICE LEVEL (FSL)



EARTHWORK

WATER CONTROL STRUCTURE

CONCRETE HEADWALL TAILWALL

REINFORCED CONCRETE PIPE

REPLACE CULVERT

EXISTING CULVERT

TEMPORARY ROAD

Dirt Balance								
Location	Cut (CY)	Fill (CY)						
Regrade Headgate	1383	1383						
Grade In Settling Basin	520							
Cleanout & Regrade Coot Ditch	710							
Temporary Road Construction		≃ 1000						
Reinforce Headgate Area		230						
Total	2613	2613						

HORIZONTAL AND VERTICAL CONTROL OPUS SOLUTION — COORDINATES ARE UTM ZONE 12 GRID COORDINATES IN US FEET [NAD83]. THEY WERE ESTABLISHED FROM THE WGS84 ELLIPSOID WITH INFORMATION FROM A TRIMBLE R10 SURVEY GRADE GPS RECEIVER ON NOVEMBER 10, 2022 AT DUCKS UNLIMITED CONTROL POINT DU—156—2022 AND CALIBRATED TO AN OPUS POSITION OCCUPIED FOR 3 HOURS AND ZY MINUTES AND SENT TO NGS FOR SOLUTION. THE VERTICAL CONTROL CAME FROM THE SAME SOLUTION USING GEOID 18 CONUS IN THE NAVD88. THE FULL OPUS SOLUTION REPORT IS ON FILE AT THE DUCKS UNLIMITED ENGINEERING DEPARTMENT IN FORT COLLINS, COLORADO.



EXAMPLE OF DUCKS UNI IMITED CONTROL POINT SURVEY CAP

ABBREVIATIONS LIST

BLDC = BUILDING CORNER
BRK = BREAK
BTM. = BOTTOM
C.L. = CENTER LINE
CMP = CORRUGATED METAL PIPE ROUND I
CONC. = CONCRETE
DIA. = DAMETER
E = EASTING COORDINATE OR EAST
ELEV. = ELEVATION

LAI = LAIIIUDL (WGS84)
LONG = LONGITUDE (WGS84)
L.F. = LINEAR FEET
MISC = MISCELLANEOUS
N = NORTHING COORDINATE OR NORTH
NFES = NON-FLARED END SECTION
O.C. = ON CENTER

O.C.E.W. = ON CENTER EACH WAY
OHE = OVERHEAD ELECTRIC
P.C. = POINT OF INTERSECTION
P.I. = POINT OF INTERSECTION
P.T. = POINT OF TANGENCY
RCP = REINFORCED CONCRETE PIPE
RD = ROAD
REM. = REMOVE
PEO'N = PROLUBED

REM. = REMOVE
REO'D = REQUIRED
R.O.W. = RIGHT OF WAY
S = SOUTH
SED. = SEDIMENT
SHLD = SHOULDER
SLP = SLOPE
STPLG = STOPLOG
TBM = TEMPORARY BENCHMARK
TEL = TELEPHONE/COMMUNICATOINS
UG = UNDERGROUND
VEG = VEGETATION
W = WEST OR WITH
WCS = WATER CONTROL STRUCTURE
WL = WATER LEVEL

WL = WATER LEVEL WS = WATER SHOT

*NOTE: NOT ALL ABBREVIATIONS IN THIS LIST APPEAR ON THIS SHEET

DU PROJECT ENGINEER: THOMAS PARKER, P.E. (970) 692-3375

GREAT PLAINS REGIONAL OFFICE P.E. SEAL; SEAL TO Engine SAMES 15300 MYONING

- 2 N 4 N 9 V 8

WETLAND 囝

OVERALL


ALPINI


04/16/2025 SHEET TITLE:
OVERALL PLAN


SCALES ARE ACCURATE ON 24"X36" SHEET SIZE III PPOJECT NIIMBED

WY-178-1 SHEET NUMBER

2 SHEET 2 OF 2







THIS MATERIAL, DATA AND INFORMATION IS THE PROPERTY OF DUCKS UNLIMITED, INC. IT MAY NOT BE USED OR REPRODUCED FOR ANY PURPOSE WITHOUT THE PRIOR WRITTEN CONSENT OF AN AUTHORIZED AGENT OF DUCKS UNLIMITED, INC. DUCKS UNLIMITED, INC. MAKES NO REPRESENTATION OR WARRANTY OF ANY KIND REGARDING THIS MATERIAL, DATA AND INFORMATION, INCLUDING, BUT NOT LIMITED TO, THE ACCURACY OF THE MATERIAL, DATA AND INFORMATION OR ITS SUITABILITY PURPOSE. ALL USE OF THE MATERIAL, DATA AND INFORMATION, USER AGREES THAT DUCKS UNLIMITED, INC. IS NOT RESPONSIBLE FOR THEIR USE OF THE MATERIAL, DATA AND INFORMATION OR THE RESULTS THEREOF.

BEFORE THE START OF CONSTRUCTION. THE OWNER OF ANY UTILITIES INVOLVED MUST BE NOTIFIED. THE EXCAVATOR/CONTRACTOR IS RESPONSIBLE FOR GIVING THIS NOTICE BY CALLING "ONE CALL OF WYOMING" AT 811.
A 72 HOUR NOTIFICATION AND FULL DESCRIPTION OF LOCATION IS REQUIRED.

THOMAS PARKER, P.E. (970) 692-3375

43'7'25,7973"N

PLAN VIEW

DU PROJECT ENGINEER:

DUCKS

REAT PLAINS REGIONAL OFFICE

SAMES SAMES 15300

MYONING

- 2 E 4 E 9 L 8

SCREW

CULVERT


FLUSHING


WY-178-1


SHEET 4 OF 2


SHEET NUMBER


P.E. SEAL:













SHEET 9 OF 20



- FILL SHALL BE OBTAINED FROM ACCEPTABLE CUT FROM COOT DITCH CLEAN-OUT, FROM SETTLING BASIN GRADING OR FROM LOCATION AS DESIGNATED BY DU CONSTRUCTION ENGINEER.
- FILL SHALL BE PLACED IN LIFTS NO MORE THAN 8" AND COMPACTED PRIOR TO PLACING SUBSEQUENT LIFTS. CONSTRUCTION OF TEMPORARY ROAD IS CONSIDERED PART OF BID ITEM "SITE PREPARATION".



TEMPORARY ROAD CONSTRUCTION SECTION SCALE 1" = 5

THIS MATERIAL, DATA AND INFORMATION IS THE PROPERTY OF DUCKS UNLIMITED, INC. IT MAY NOT BE USED OR REPRODUCED FOR ANY PURPOSE WITHOUT THE PRIOR WRITTEN CONSENT OF AN AUTHORIZED AGENT OF DUCKS UNLIMITED, INC. DUCKS UNLIMITED, INC. MAKES NO REPRESENTATION OR WARRANTY OF ANY KIND REGARDING THIS MATERIAL, DATA AND INFORMATION, INCLUDING, BUT NOT LIMITED TO, THE ACCURACY OF THE MATERIAL, DATA AND INFORMATION OR ITS SUITABILITY PURPOSE. ALL USE OF THE MATERIAL, DATA AND INFORMATION, USER AGREES THAT DUCKS UNLIMITED, INC. IS NOT RESPONSIBLE FOR THEIR USE OF THE MATERIAL, DATA AND INFORMATION OR THE RESULTS THEREOF.

BEFORE THE START OF CONSTRUCTION. THE OWNER OF ANY UTILITIES INVOLVED MUST BE NOTIFIED. THE EXCAVATOR/CONTRACTOR IS RESPONSIBLE FOR GIVING THIS NOTICE BY CALLING "ONE CALL OF WYOMING" AT 811.
A 72 HOUR NOTIFICATION AND FULL DESCRIPTION OF LOCATION IS REQUIRED.

DU PROJECT ENGINEER: THOMAS PARKER, P.E. (970) 692-3375

WETLANDS ALPINE

ROAD

TITLE: TEMPORARY


04/16/2025


SHEET TITLE: TEMPORARY ROAD CONSTRUCTION


SCALES ARE ACCURATE ON 24"X36" SHEET SIZE DU PROJECT NUMBER:

WY-178-1 SHEET NUMBER:

10 SHEET 10 OF 20







THE DRAWINGS PRESENTED HERE FROM CONTECH ENGINEERING SOLUTIONS LLC ARE PRELIMINARY - NOT FOR CONSTRUCTION". CONTRACTOR TO REACH OUT TO CONTECH

LEGEND PROPERTY BOUNDARY **EARTHWORK** CONCRETE HEADWALL/ TAILWALL SCREW GATE REINFORCED CONCRETE PIPE REPLACE CULVERT RIPRAP

DU PROJECT ENGINEER:

THOMAS PARKER, P.E.

(970) 692-3375

TEMPORARY ROAD

WETLANDS ALPINE

SHEETS

DESIGN

CULVERT

T TITLE:
CONTECH DATE: 04/16/2025

CONTECH |CULVERT DESIGN SHEETS 1-2


SCALES ARE ACCURATE ON 24"X36" SHEET SIZE DU PROJECT NUMBER:


> WY-178-1 SHEET NUMBER:

11A

BEFORE THE START OF CONSTRUCTION. THE OWNER OF ANY UTILITIES INVOLVED MUST BE NOTIFIED. THE EXCAVATOR/CONTRACTOR IS RESPONSIBLE FOR GIVING THIS NOTICE BY CALLING "ONE CALL OF WYOMING" AT 811.

A 72 HOUR NOTIFICATION AND FULL DESCRIPTION OF LOCATION IS REQUIRED.





THE DRAWINGS PRESENTED HERE FROM CONTECH ENGINEERING SOLUTIONS LLC ARE "PRELIMINARY — NOT FOR CONSTRUCTION". CONTRACTOR TO REACH OUT TO CONTECH FOR FINAL DESIGN DRAWINGS.

PROPERTY BOUNDARY

EARTHWORK

CONCRETE HEADWALL/
TAILWALL

SCREW GATE

REINFORCED CONCRETE PIPE

REPLACE CULVERT

RIPRAP

DU PROJECT ENGINEER:

THOMAS PARKER, P.E. (970) 692-3375

TEMPORARY ROAD

PROJECT:

DATE:
04/16/2025
SHEET TITLE:
CONTECH
CULVERT
DESIGN
SHEETS 3-4

WETLANDS

ALPINE

က်

SHEETS

DESIGN

CULVERT

T TITLE: CONTECH

SCALES ARE ACCURATE ON 24"X36" SHEET SIZE

WY-178-1

SHEET NUMBER:


11B
SHEET11B OF 20


"PEROPE VOIL DIG"


BEFORE THE START OF CONSTRUCTION. THE OWNER OF ANY UTILITIES INVOLVED MUST BE NOTIFIED. THE EXCAVATOR/CONTRACTOR IS RESPONSIBLE FOR GIVING THIS NOTICE BY CALLING "ONE CALL OF WYOMING" AT 811.

A 72 HOUR NOTIFICATION AND FULL DESCRIPTION OF LOCATION IS REQUIRED.

THIS MATERIAL, DATA AND INFORMATION IS THE PROPERTY OF DUCKS UNLIMITED, INC. IT MAY NOT BE USED OR REPRODUCED FOR ANY PURPOSE WITHOUT THE PRIOR WRITTEN CONSENT OF AN AUTHORIZED AGENT OF DUCKS UNLIMITED, INC. DUCKS UNLIMITED, INC. MAKES NO REPRESENTATION OR WARRANTY OF ANY KIND REGARDING THIS MATERIAL, DATA AND INFORMATION, INCLUDING, BUT NOT LIMITED TO, THE ACCURACY OF THE MATERIAL, DATA AND INFORMATION OR ITS SUITABILITY FOR ANY PURPOSE. ALL USE OF THE MATERIAL, DATA AND INFORMATION INFORMATION, USER AGREES THAT DUCKS UNLIMITED, INC. IS NOT RESPONSIBLE FOR THEIR USE OF THE MATERIAL, DATA AND INFORMATION OR THE RESULTS THEREOF.







THE DRAWINGS PRESENTED HERE FROM CONTECH ENGINEERING SOLUTIONS LLC ARE "PRELIMINARY - NOT FOR CONSTRUCTION". CONTRACTOR TO REACH OUT TO CONTECH FOR FINAL DESIGN DRAWINGS.

PROPERTY BOUNDARY

EARTHWORK

CONCRETE HEADWALL/
TAILWALL

SCREW GATE

REINFORCED CONCRETE PIPE

REPLACE CULVERT

RIPRAP

TEMPORARY ROAD

DU PROJECT ENGINEER:

THOMAS PARKER, P.E. (970) 692-3375

ALPINE WETLANDS

SHEET TITLE:
CONTECH CULVERT

5-6

SHEETS

DESIGN

DATE: 04/16/2025
SHEET TITLE: CONTECH CULVERT DESIGN SHEETS 5-6

SCALES ARE ACCURATE ON 24"X36" SHEET SIZE

WY-178-1

SHEET NUMBER:

1 1 C


SHEET1 1C OF 20


"BEFORE YOU DIG'


BEFORE THE START OF CONSTRUCTION. THE OWNER OF ANY UTILITIES INVOLVED MUST BE NOTIFIED. THE EXCAVATOR/CONTRACTOR IS RESPONSIBLE FOR GIVING THIS NOTICE BY CALLING "ONE CALL OF WYOMING" AT 811.

A 72 HOUR NOTIFICATION AND FULL DESCRIPTION OF LOCATION IS REQUIRED.

THIS MATERIAL, DATA AND INFORMATION IS THE PROPERTY OF DUCKS UNLIMITED, INC. IT MAY NOT BE USED OR REPRODUCED FOR ANY PURPOSE WITHOUT THE PRIOR WRITTEN CONSENT OF AN AUTHORIZED AGENT OF DUCKS UNLIMITED, INC. DUCKS UNLIMITED, INC. MAKES NO REPRESENTATION OR WARRANTY OF ANY KIND REGARDING THIS MATERIAL, DATA AND INFORMATION, INCLUDING, BUT NOT LIMITED TO, THE ACCURACY OF THE MATERIAL, DATA AND INFORMATION OR ITS SUITABILITY PURPOSE. ALL USE OF THE MATERIAL, DATA AND INFORMATION, USER AGREES THAT DUCKS UNLIMITED, INC. IS NOT RESPONSIBLE FOR THEIR USE OF THE MATERIAL, DATA AND INFORMATION OR THE RESULTS THEREOF.







THE DRAWINGS PRESENTED HERE FROM CONTECH ENGINEERING SOLUTIONS LLC ARE PRELIMINARY - NOT FOR CONSTRUCTION". CONTRACTOR TO REACH OUT TO CONTECH

LEGEND PROPERTY BOUNDARY **EARTHWORK** CONCRETE HEADWALL/ TAILWALL SCREW GATE REINFORCED CONCRETE PIPE REPLACE CULVERT RIPRAP

DU PROJECT ENGINEER:

THOMAS PARKER, P.E.

(970) 692-3375

TEMPORARY ROAD

 Ω WETLAND Ξ **ALPINI**

WYONING

æ

SHEETS

DESIGN

CULVERT

T TITLE:
CONTECH

04/16/2025 CONTECH |CULVERT DESIGN SHEETS 7-8


SCALES ARE ACCURATE ON 24"X36" SHEET SIZE DII PROJECT NUMBER


WY-178-1 SHEET NUMBER:


11D SHEETI 1D OF 20

BEFORE THE START OF CONSTRUCTION. THE OWNER OF ANY UTILITIES INVOLVED MUST BE NOTIFIED. THE EXCAVATOR/CONTRACTOR IS RESPONSIBLE FOR GIVING THIS NOTICE BY CALLING "ONE CALL OF WYOMING" AT 811.
A 72 HOUR NOTIFICATION AND FULL DESCRIPTION OF LOCATION IS REQUIRED.

THIS MATERIAL, DATA AND INFORMATION IS THE PROPERTY OF DUCKS UNLIMITED, INC. IT MAY NOT BE USED OR REPRODUCED FOR ANY PURPOSE WITHOUT THE PRIOR WRITTEN CONSENT OF AN AUTHORIZED AGENT OF DUCKS UNLIMITED, INC. DUCKS UNLIMITED, INC. MAKES NO REPRESENTATION OR WARRANTY OF ANY KIND REGARDING THIS MATERIAL, DATA AND INFORMATION, INCLUDING, BUT NOT LIMITED TO, THE ACCURACY OF THE MATERIAL, DATA AND INFORMATION OR ITS SUITABILITY PURPOSE. ALL USE OF THE MATERIAL, DATA AND INFORMATION, USER AGREES THAT DUCKS UNLIMITED, INC. IS NOT RESPONSIBLE FOR THEIR USE OF THE MATERIAL, DATA AND INFORMATION OR THE RESULTS THEREOF.







THE DRAWINGS PRESENTED HERE FROM CONTECH ENGINEERING SOLUTIONS LLC ARE "PRELIMINARY - NOT FOR CONSTRUCTION". CONTRACTOR TO REACH OUT TO CONTECH FOR FINAL DESIGN DRAWINGS.

LEGEND PROPERTY BOUNDARY **EARTHWORK** CONCRETE HEADWALL TAILWALL SCREW GATE REINFORCED CONCRETE PIPE REPLACE CULVERT RIPRAP

DU PROJECT ENGINEER:

THOMAS PARKER, P.E.

(970) 692-3375

WETLANDS

TEMPORARY ROAD

DATE: 04/16/2025 SHEET TITLE: CONTECH CULVERT DESIGN SHEETS 9-10

ALPINE

SHEETS

DESIGN

CULVERT

ET TITLE: CONTECH


SCALES ARE ACCURATE ON 24"X36" SHEET SIZE DU PROJECT NUMBER:


WY-178-1 SHEET NUMBER:


11ESHEETI 1E OF 20

BEFORE THE START OF CONSTRUCTION. THE OWNER OF ANY UTILITIES INVOLVED MUST BE NOTIFIED. THE EXCAVATOR/CONTRACTOR IS RESPONSIBLE FOR GIVING THIS NOTICE BY CALLING "ONE CALL OF WYOMING" AT 811.
A 72 HOUR NOTIFICATION AND FULL DESCRIPTION OF LOCATION IS REQUIRED.

THIS MATERIAL, DATA AND INFORMATION IS THE PROPERTY OF DUCKS UNLIMITED, INC. IT MAY NOT BE USED OR REPRODUCED FOR ANY PURPOSE WITHOUT THE PRIOR WRITTEN CONSENT OF AN AUTHORIZED AGENT OF DUCKS UNLIMITED, INC. DUCKS UNLIMITED, INC. MAKES NO REPRESENTATION OR WARRANTY OF ANY KIND REGARDING THIS MATERIAL, DATA AND INFORMATION, INCLUDING, BUT NOT LIMITED TO, THE ACCURACY OF THE MATERIAL, DATA AND INFORMATION OR ITS SUITABILITY PURPOSE. ALL USE OF THE MATERIAL, DATA AND INFORMATION, USER AGREES THAT DUCKS UNLIMITED, INC. IS NOT RESPONSIBLE FOR THEIR USE OF THE MATERIAL, DATA AND INFORMATION OR THE RESULTS THEREOF.








ROCK CHECK SECTION CUT (PINTAIL RESERVOIR)

SCALE 1"=5"



ROCK CHECK PROFILE VIEW (PINTAIL RESERVOIR)

SCALE 1"=5"

SPILLWAY INVERT
ELEV. = 5,623.0

TOP OF ROCK SPILLWAY


(INVERT WIDTH)

10 CUBIC YARDS OF DU

CLASS II ROCK RIPRAP WITH
FILTER FABRIC BENEATH.

ARMORED SPILLWAY SECTION CUT (PINTAIL RESERVOIR)

SCALE 1"=5"



ARMORED SPILLWAY PROFILE VIEW (PINTAIL RESERVOIR)

SCALE 1"=5"

THIS MATERIAL, DATA AND INFORMATION IS THE PROPERTY OF DUCKS UNLIMITED, INC. IT MAY NOT BE USED OR REPRODUCED FOR ANY PURPOSE WITHOUT THE PRIOR WRITTEN CONSENT OF AN AUTHORIZED AGENT OF DUCKS UNLIMITED, INC. DUCKS UNLIMITED, INC. MAKES NO REPRESENTATION OR WARRANTY OF ANY KIND REGARDING THIS MATERIAL, DATA AND INFORMATION, INCLUDING, BUT NOT LIMITED TO, THE ACCURACY OF THE MATERIAL, DATA AND INFORMATION OR ITS SUITABILITY PURPOSE. ALL USE OF THE MATERIAL, DATA AND INFORMATION, USER AGREES THAT DUCKS UNLIMITED, INC. IS NOT RESPONSIBLE FOR THEIR USE OF THE MATERIAL, DATA AND INFORMATION OR THE RESULTS THEREOF.

"BEFORE YOU DIG"

BEFORE THE START OF CONSTRUCTION. THE OWNER OF ANY UTILITIES INVOLVED MUST BE NOTIFIED. THE EXCAVATOR/CONTRACTOR IS RESPONSIBLE FOR GIVING THIS NOTICE BY CALLING "ONE CALL OF WYOMING" AT 811.

A 72 HOUR NOTIFICATION AND FULL DESCRIPTION OF LOCATION IS REQUIRED.

DU PROJECT ENGINEER: THOMAS PARKER, P.E. (970) 692-3375

ALPINE WETLANDS

ALPINE WETLANDS

SHEET TITLE: PINTAIL RESERVOIR

ARMORED SPILLWAY & ROCK


SCALES ARE ACCURATE ON 24"X36" SHEET SIZE


SPILLWAY &


ROCK CHECK

WY-178-1
SHEET NUMBER:


13 SHEET 13 OF 20







AMORED SPILLWAY SECTION CUT (MERGANSER RESERVOIR) SCALE 1"=5'



ARMORED SPILLWAY PROFILE VIEW (MERGANSER RESERVOIR)



THIS MATERIAL, DATA AND INFORMATION IS THE PROPERTY OF DUCKS UNLIMITED, INC. IT MAY NOT BE USED OR REPRODUCED FOR ANY PURPOSE WITHOUT THE PRIOR WRITTEN CONSENT OF AN AUTHORIZED AGENT OF DUCKS UNLIMITED, INC. DUCKS UNLIMITED, INC. MAKES NO REPRESENTATION OR WARRANTY OF ANY KIND REGARDING THIS MATERIAL, DATA AND INFORMATION, INCLUDING, BUT NOT LIMITED TO, THE ACCURACY OF THE MATERIAL, DATA AND INFORMATION OR ITS SUITABILITY PURPOSE. ALL USE OF THE MATERIAL, DATA AND INFORMATION, USER AGREES THAT DUCKS UNLIMITED, INC. IS NOT RESPONSIBLE FOR THEIR USE OF THE MATERIAL, DATA AND INFORMATION OR THE RESULTS THEREOF.

BEFORE THE START OF CONSTRUCTION. THE OWNER OF ANY UTILITIES INVOLVED MUST BE NOTIFIED. THE EXCAVATOR/CONTRACTOR IS RESPONSIBLE FOR GIVING THIS NOTICE BY CALLING "ONE CALL OF WYOMING" AT 811.
A 72 HOUR NOTIFICATION AND FULL DESCRIPTION OF LOCATION IS REQUIRED.


DU PROJECT ENGINEER: THOMAS PARKER, P.E. (970) 692-3375


SCALES ARE ACCURATE ON 24"X36" SHEET SIZE DU PROJECT NUMBER: WY-178-1


RESERVOIR SPILLWAY

MERGANSER ARMORED

SHEET NUMBER: 15 SHEET 15 OF 20







FOR GIVING THIS NOTICE BY CALLING "ONE CALL OF WYOMING" AT 811.

A 72 HOUR NOTIFICATION AND FULL DESCRIPTION OF LOCATION IS REQUIRED.

ABBREVIATIONS LIST

O.C.E.W. = ON CENTER EACH WAY
OHE = OVERHEAD ELECTRIC
P.C. = POINT OF INTERSECTION
P.I. = POINT OF INTERSECTION
P.I. = POINT OF TANGENCY
RCP = REINFORCED CONCRETE PIPE
RD = ROAD
REM. = REMOVE
REO'D = REQUIRED
R.O.W. = RIGHT OF WAY
S = SOUTH
SED. = SEDIMENT
SHLD = SHOULDER
SLP = SLOPE
STPLG = STOPLOG
TBM = TEMPORARY BENCHMARK
TEL = TELEPHONE/COMMUNICATOINS
UG = UNDERGROUND
WE WEST OR WITH
WCS = WATER LEVEL
WS = WATER LEVEL
WS = WATER LEVEL
WS = WATER LANDERVATIONS IN

*NOTE: NOT ALL ABBREVIATIONS IN THIS LIST APPEAR ON THIS SHEET

DU PROJECT ENGINEER: THOMAS PARKER, P.E. (970) 692-3375



WYONING



WETLANDS CONTROL

ALPINE

TRAFFIC


DATE: 04/16/2025

SHEET TITLE: TRAFFIC CONTROL PLAN

SCALES ARE ACCURATE ON 24"X36" SHEET SIZE

DU PROJECT NUMBER: WY-178-1

SHEET NUMBER: 18 SHEET 18 OF 20



						10-	
STORM WATER POLLUTION PREVENTION PLAN WYPDES Permit #) issued on / shall apply	(Check all that apply) When chest are stabilization Practices	JCTION CHANGES anges are made to the construction project require alterations in the temporary erosion			MAINTENANCE AND INSPECTION Maintenance and Inspection Practices Inspections will be conducted at least one time per		3
for this project.	Temporary or Permanent Seeding controls Sod Placement	of the site, the Storm Water Pollution n Plan (SWPPP) will be amended to provide			week and after a storm event of 0.50 inches or areater.		
ABBREVIATIONS	Planting Mulching (Straw or Cellulose Fiber) appropria	tte protection to disturbed areas, all storm ructures, and adjacent waters. The SWPPP will			 All controls will be maintained in good working order. Necessary repairs will be initiated within 24 	DIII	∪K∠ '®
WDEQ: Wyoming Department of Environmental Quality WYPDES: Wyoming Pollution Discharge Elimination	X Vegetation Buffer Strips be retain	ed in a designated place for review over the			hours of the site inspection report or as soon as field conditions allow access.	บที่ผู้ใ	CKS MITED
System USFWS: United States Fish and Wildlife Service	Rougnened Surface (e.g. tracking) Online Online Methods	f the project.			 Where work has been suspended due to frozen 	GREAT PLAINS	IC. REGIONAL O
SWMP: Storm Water Management Plan	• _X Other: Rip Rap				ground conditions, the required inspections and maintenance must take place as soon as runoff	P.E. SEAL:	Fngina
LOCATION/NARRATIVE	Structural Temporary Erosion and Sediment Controls • Silt Fence				occurs at the site or prior to resuming construction, whichever comes first.	designal 1	Engineer C
Location: See Sheet 1 for the location of this project.	Temporary Berm Temporary Slope Drain	DAILY STORMWATER	POLLUTION PREVENTION PLAN L	<u>.0G B00K</u>	Where parts of the construction site have undergone final stabilization, but work remains on other parts		5300多
Project Limits: See Sheet 2 of this plan for the	Straw Wattles or Rolls Diversion Channels/Swales	CWDDD ADMINISTRATOR			of the site, inspections of the stabilized areas may be reduced to once per month.		
project limits. This sheet covers the earthwork, water control structures and rock riprap.	Channel Liners (TRM)	SWPPP ADMINISTRATOR: INSPECTOR:	DATE /TIME.		Silt fence will be inspected for depth of sediment		ONING
PROJECT CONTACTS	Stone Rip Rap Sheet X Rock Check Dams	INSI ECTOR:	DATE/ TIME.		and for tears in order to ensure the fabric is securely anchored. Sediment buildup will be		
SWPPP Administrator: Thomas Parker, P.E.	Sediment Traps/Basins X Inlet Protection	INSPECTION ITEMS:			removed from the silt fence when it reaches ½ of the height of the silt fence. All silt fences must		
Ducks Unlimited Cell: 970–692–3375	X Outlet Protection Surface Inlet Protection	Inlet Filters			be repaired, replaced, or supplemented when they become nonfunctional or the sediment reaches k of	BY: KJW f: JJW	1.1.
Email: tparker@ducks.org	Curb Inlet Protection Stabilized Construction Entrances	Straw Bale Dikes Silt Fence			the height of the fence. Sediment basins and traps will be checked.	DESIGNED BY: DRAWN BY: SURVEYED BY:	<u> </u>
The Contractor is responsible for implementation of the	• Other	Pond Outlet			Sediment will be removed when the depth reaches	GNED MN BY:	CHECKED B
SWPPP and installation, inspection and maintenance of the erosion prevention and sediment control BMP's	<u>DESCRIPTION OF CONSTRUCTION ACTIVITIES</u> The proposed construction activities will provide	Vehicle Tracking Pad			 approximately 50 percent of the structure's capacity. Check dams will be inspected for stability. 	SUR PR	
before and during construction.	water level management to the site. Through this	Pond Sediment Surface Erosion			Sediment will be removed when the depth reaches % the height of the dam.		亓
Contractor Name:	management more desirable wetlands will be created.	Surface Erosion Riprap Structures			 All seeded areas will be checked for bare spots, washouts, and vigorous growth free of significant 		
Company: Telephone Number:	Major Soil Disturbing Activities (check all that apply): X Clearing & Grubbing	Drainage Pans			weed infestations. Surface waters, including drainage ditches and		+++
Email:	X Grading & Shaping X Cutting & Filling	REPAIRS OR MAINTENANCE NEEDED:			conveyance systems, must be inspected for evidence		
SPILL NOTIFICATION In the event of a spill, the contractor's site	• Other (describe):	NEITHIO ON MAINTENANCE NEEDED.			of sediment being deposited by erosion. Construction site vehicle exit locations must be	DATE	
superintendent will make the appropriate notificiaton(s), consistent with the following procedures:	ORDER OF CONSTRUCTION ACTIVITIES				inspected for evidence of off—site sediment tracking onto paved surfaces. Tracked sediment must be		
1. A reportable spill is a quantity of 25 gallons of	(Stabilization measures shall be initiated as soon as possible,	REPAIRS OR MAINTENANCE MADE:			removed from all off-site paved surfaces within 24 hours of discovery.		
petroleum which must be reported immediately to the DEQ Water Quality Division.	but in no case later than 14 days after the construction activity in that portion of the site has temporarily or	TELLY MICE OF THE MICE THE SELECTION OF			Disturbed areas will be checked for stabilization. Stabilization measures shall be initiated as soon as	ijoji Noji	
Any spill of oil or hazardous substance to waters of the state must be reported immediately.	permanently ceased.) Install initial erosion and sediment control measures.				construction activity in that portion of the site has temporarily or permanently ceased.	REVIEW REVIEW	
 Wyoming Department of Environmental Quality's Spill and Complaint: 	 Proceed with site grading and construction activities. Stabilize areas disturbed by construction activities with 				The normal wetted perimeter of any temporary or	- 0 m 4	
DEQSpills.wyo.gov —or— 24 Hour (307) 777—7781 4. Within 7 days following a release, submit a written	temporary erosion and sediment control measures. Install water control structure.	MAINTENANCE ITEMS:			permanent drainage ditch or swale that drains water from any portion of the construction site, or divers		l l
report to the DEQ Water Quality Division describing the reportable release, the response, and the steps	 Complete final grading. 				water around the site, must be stabilized within 200 lineal feet from the property edge, or from the		
taken to prevent recurrence.	 Complete permanent erosion and sediment control measures. 				point of discharge into any surface water. Stabilization of the last 200 lineal feet must be		
POTENTIAL POLLUTION SOURCES	ESTIMATED PROJECT AREA QUANTITIES	CONTACTS MADE:	AGENCY:		completed within 24 hours after connection to a surface water.		
Heavy machinery will be operated on the project site requiring the use of fuel trucks. Contamination due	Total Project Area: 189 Acres Total Area to Be Disturbed: 4.8 Acres	MATERIALS HANDLING:			Stabilization of the remaining portions of any temporary or permanent ditches or swales must be	\mathbb{N}	
to fuel spills and oil leaks is possible due to the large volume of work being performed. Day to day	Existing Impervious Area: 0.0 Acres Proposed Impervious Area: 0.0 Acres	ITEMS DELIVERED:			completed within 14 days after connecting to a surface water and construction in that portion of		
cleaning and maintenance of equipment has the potential to impact stormwater quality. Delivery of	EXISTING GROUND COVER	ACTIONS TAKEN:			the ditch has temporarily or permanently ceased. Temporary or permanent ditches or swales that are		۷ ا
site materials also has potential for impacting runoff	Currently the site is mostly native grass and trees. There are six existing wetlands on—site. Water is managed in	ACTIONS TAKEN.			being used as a sediment containment system (with	TLAND	E
quality. Another potential pollution source is sediment transport from earthwork.	the reservoirs using water control structures.	SPILL REPORTING:			properly designed rock ditch checks, bio rolls, silt dikes, etc.) do not need to be stabilized. These		
POLLUTION PREVENTION MANAGEMENT MEASURES	NON-STORMWATER DISCHARGE	MATERIAL SPILLED:			areas must be stabilized within 24 hours after no longer being used as a sediment containment	WE	
Solid Wastes (None anticipated): Collected sediment, asphalt, and concrete millings,	None.	WHY MATERIAL SPILLED:			system. • Pipe outlets must be provided with temporary or		
floating debris, paper, plastic, fabric, construction and demolition debris and other wastes must be disposed of	RECEIVING WATER Runoff from the site is retained by the existing reservoir	QUANTITY:			permanent energy dissipation within 24 hours after connection to a surface water.		
properly and must comply with the DEQ Water Quality Division disposal requirements.	outlet works. During a flooding event, water from the project area would ultimately drain into the Shoshone River.	QUANTITY:			 Discharge procedures for water control and dewatering operations will be inspected. If the 		"
Hazardous Materials (None anticipated):	STREAM CROSSINGS LOCATED WITHIN THE CONSTRUCTION SITE	LOCATION:			water cannot be discharged to a sedimentation basin prior to entering the surface water, it must	ALPINE	
Oil, gasoline, paint and any hazardous substances must be properly stored, including secondary	BOUNDARY	WEATHER CONDITIONS:			be treated with the appropriate BMPs, such that the discharge does not adversely affect the receiving	₹	
containment, to prevent spills, leaks or other discharge. Restricted access to storage areas must be provided to	None.				water or downstream landowners.		١
prevent vandalism. Storage and disposal of hazardous waste must be in compliance with DEQ Water Quality	LOCATION OF SWPPP REQUIREMENTS IN PROJECT PLAN See the Erosion and Sediment Control notes and details	SPILL START TIME:	SPILL STOP TIME:	AM/PM	 Inspection and maintenance reports will be completed for each site inspection, this form will 	1	
Division regulations. • Vehicle Washing:	on the Stormwater Pollution Prevention Plan sheets.	CLEANUP METHOD:			also be used to document changes to the SWMP. The report shall include the date and amount of	ECT	
External washing of trucks and other construction vehicles must be limited to a defined area of the	FINAL STABILIZATION AND LONGTERM STORMWATER MANAGEMENT	CLD WAS METHOD!			precipitation or snowmelt events that cause surface erosion. A copy of the completed inspection form	₽	SHEET
site. Runoff must be contained and waste properly disposed of. No engine degreasing is allowed on	Following site construction, the goal is to achieve a	DISPOSAL METHOD:			will be filed with the SWMP documents. The Contractor's site superintendent is responsible	DATE:	<u> </u>
site.	stabilized cover condition to provide long—term stormwater protection. Stabilization is quantified by	DISPOSAL METHOD.			for inspection. Maintenance and repair activities are the responsibility of the Contractor.	04/16/2 SHEET TITLE:	025
Concrete Washout Onsite (No concrete anticipated): All liquid and solid wastes generated by concrete	achieving uniform cover equal to 70% of the pre—disturbance condition. The post—construction				and the second second second	SWPPP N	OTES
washout operation must be contained in a leak-proof containment facility or impermeable liner. A compacted	condition of the site shall be that the majority of the disturbed area will be compacted soil and seeded. Once	ENTER N/A IF ITEM IS NOT APPLICAL	BLE 10 THE SITE SWPPP.				
clay liner that does not allow washout liquids to enter ground water is considered an impermeable liner. The	the seeding takes, this shall virtually eliminate erosion from the site. Permanent seeding with mulching is				_		
liquid and solid wastes must not contact the ground, and there must not be runoff from the concrete	installed as needed. Drainage ditches, pans, and culverts						
washout operation or areas. Liquid and solid wastes must be disposed of properly and in compliance with	shall be cleaned of debris and sediment. Repair eroded sloped or drainage paths by backfilling. Remove all silt						
DEQ Water Quality Division regulations. A sign must be installed adjacent to each washout facility to inform	fences following establishment of permanent stable vegetation.					SCALES ARE 24"X36" SHE	ACCURATE FT SIZE
concrete equipment operators to utilize the proper facilities.						DU PROJECT	NUMBER:
						11 10737 4	. ~ ~


"BEFORE YOU DIG"

BEFORE THE START OF CONSTRUCTION. THE OWNER OF ANY UTILITIES INVOLVED MUST BE NOTIFIED. THE EXCAVATOR/CONTRACTOR IS RESPONSIBLE FOR GIVING THIS NOTICE BY CALLING "ONE CALL OF WYOMING" AT 811.

A 72 HOUR NOTIFICATION AND FULL DESCRIPTION OF LOCATION IS REQUIRED.

THIS MATERIAL, DATA AND INFORMATION IS THE PROPERTY OF DUCKS UNLIMITED, INC. IT MAY NOT BE USED OR REPRODUCED FOR ANY PURPOSE WITHOUT THE PRIOR WRITTEN CONSENT OF AN AUTHORIZED AGENT OF DUCKS UNLIMITED, INC. DUCKS UNLIMITED, INC. MAKES NO REPRESENTATION OR WARRANTY OF ANY KIND REGARDING THIS MATERIAL, DATA AND INFORMATION, INCLUDING, BUT NOT LIMITED TO, THE ACCURACY OF THE MATERIAL, DATA AND INFORMATION OR ITS SUITABILITY FOR ANY PURPOSE. ALL USE OF THE MATERIAL, DATA AND INFORMATION, USER AGREES THAT DUCKS UNLIMITED, INC. IS NOT RESPONSIBLE FOR THEIR USE OF THE MATERIAL, DATA AND INFORMATION OR THE RESULTS THEREOF.

DU PROJECT ENGINEER: THOMAS PARKER, P.E. (970) 692-3375



WY-178-1 SHEET NUMBER:

20 SHEET 20 OF 20