

2114 MIDPOINT POINT DR. SUITE 1 FORT COLLINS, CO 80525

ESTIMATED QUANTITIES

SITE PREPARATION (TOP SOIL):

MOBILIZATION:

DEWATERING:

EXCAVATION:

GRADE IN SETTLING BASIN CLEANOUT & REGRADE COOT DITCH	520 C,YP 710 C.YP
CONSTRUCTED TOPOGRAPHY: RE-GRADE HEADGATE AREA REINFORCE HEADGATE AREA	1,383 C.YF 230 C.YP
WATER CONTROL STRUCTURES (WCS) - SUPPLY & INSTALL: 48"ø FRESNO SERIES 6600 MODEL 101C SCREW GATE (12' TALL) 36"ø FRESNO SERIES 6600 MODEL 101C SCREW GATE (12' TALL) 24"ø (5' TALL) INLINE WCS	
CULVERTS & PIPE - SUPPLY & INSTALL: ALBC ALUMINUM BOX CULVERT (16'-10" SPAN x 8'-3" RISE x 45'-3" LENGTH) 48"Ø REINFORCED CONCRETE PIPE 36"Ø REINFORCED CONCRETE PIPE 24"Ø PVC PIPE (SDR 51)	1 EA. 25 L.FA 35 L.FA 52 L.FA
CAST-IN-PLACE REINFORCED CONCRETE: REINFORCED CONCRETE FLUSHING CULVERT HEADWALL REINFORCED CONCRETE HEADWALL/TAILWALL REINFORCED CONCRETE TAILWALL	1 EA. 1 EA. 1 EA.
ROCK, RIPRAP, & REVETMENT - SUPPLY & PLACE: DU CLASS IV ROCK RIPRAP W/ FILTER FABRIC DU CLASS II ROCK RIPRAP W/ FILTER FABRIC ROCK PITRUN WELL-GRADED SAND 1" MINUS ANGULAR GRANULAR AGGREGATE	40 C.YP 135 C.YP 25 C.YP 11.5 C.YP 12 C.YP
MISCELLANEOUS MAINTENANCE/DISPOSAL: REMOVAL & OFFSITE DISPOSAL OF EXISTING PIPE & WATER CONTROL STRUCTURES	1 L.S.
TRAFFIC MAINTENANCE AND CONTROL	4 7 0

C.Y.-P - PAYMENT WILL BE BASED ON THE PLAN QUANTITY LISTED ABOVE. L.F.-A - PAYMENT WILL BE BASED ON ACTUAL QUANTITY EXCAVATED, FILLED, RE-GRADED, CLEANED OUT, OR SUPPLIED AND INSTALLED

SPECIFICATIONS

101	GENERAL	CONDITIONS
101	GLITTILL	COLIDITIONS

SUPPLEMENTAL CONDITIONS

SIGNAGE & EQUIPMENT

MOBILIZATION

SITE PREPARATION

EXCAVATION

CONSTRUCTED TOPOGRAPHY

WATER CONTROL STRUCTURES

CULVERT AND PIPE INSTALLATION CAST-IN-PLACE REINFORCED CONCRETE

INSTALL & MAINTAIN TRAFFIC CONTROL SIGNALS,

RIPRAP, REVETMENT & AGGREGATE PLACEMENT

SHEET PILING

REMOVAL OF EXISTING CULVERTS AND STRUCTURES

SOIL EROSION AND POLLUTION CONTROL


TRAFFIC MAINTENANCE AND CONTROL

DUCKS UNLIMED

PROJECT

ALPINE WETLANDS

LOCATED IN PARTS OF SECTIONS 3, 4, & 10 TOWNSHIP 36N, RANGE 119W, 6TH P.M., LINCOLN COUNTY, WYOMING 7




"BEFORE YOU DIG"

BEFORE THE START OF CONSTRUCTION. THE OWNER OF ANY UTILITIES

FOR GIVING THIS NOTICE BY CALLING "ONE CALL OF WYOMING" AT 811.


INVOLVED MUST BE NOTIFIED. THE EXCAVATOR/CONTRACTOR IS RESPONSIBLE

A 72 HOUR NOTIFICATION AND FULL DESCRIPTION OF LOCATION IS REQUIRED




PLAN INDEX

- TITLE PAGE & LOCATION MAP
- OVERALL PLAN
- FLUSHING CULVERT HEADWALL
- FLUSHING CULVERT SCREW GATE
- MAIN HEADWALL
- MAIN SCREW GATE
- MAIN TAILWALL
- REGRADE HEADGATE AREA, MOVE EX. ROCK PENINSULA & GRADE-IN SETTLING BASIN
- CLEANOUT & REGRADE COOT DITCH
- TEMPORARY ROAD CONSTRUCTION
- 11 ROAD CULVERT REPLACEMENT
- 11A CONTECH CULVERT DESIGN SHEETS 1-2
- 11B CONTECH CULVERT DESIGN SHEETS 3-4
- 11C CONTECH CULVERT DESIGN SHEETS 5-6
- 11D CONTECH CULVERT DESIGN SHEETS 7-8
- 11E CONTECH CULVERT DESIGN SHEETS 9-10
- 12 RUDDY DUCK RESERVOIR ARMORED SPILLWAY
- PINTAIL RESERVOIR ARMORED SPILLWAY & ROCK CHECK
- TEAL RESERVOIR ARMORED SPILLWAY
- MERGANSER RESERVOIR ARMORED SPILLWAY
- GOLDENEYE RESERVOIR ARMORED SPILLWAY
- GOLDENEYE WCS REPLACEMENT
- TRAFFIC CONTROL PLAN
- 19 STORMWATER POLLUTION PREVENTION PLAN



DU PROJECT ENGINEER: THOMAS PARKER, P.E. (970) 692-3375



SCALES ARE ACCURATE ON

WY - 178 - 1

SHEET 1 OF 20

24"X36" SHEET SIZE

DU PROJECT NUMBER:

SHEET NUMBER


THIS MATERIAL, DATA AND INFORMATION IS THE PROPERTY OF DUCKS UNLIMITED, INC. IT MAY NOT BE USED OR REPRODUCED FOR ANY PURPOSE WITHOUT THE PRIOR WRITTEN CONSENT OF AN AUTHORIZED AGENT OF DUCKS UNLIMITED, INC. DUCKS UNLIMITED, INC. MAKES NO REPRESENTATION OR WARRANTY OF ANY KIND REGARDING THIS MATERIAL, DATA AND INFORMATION, INCLUDING, BUT NOT LIMITED TO, THE ACCURACY OF THE MATERIAL, DATA AND INFORMATION OR ITS SUITABILITY FOR ANY PURPOSE. ALL USE OF THE MATERIAL, DATA AND INFORMATION IS AT THE USERS SOLE RISK. BY USING ANY OF THIS MATERIAL, DATA AND INFORMATION, USER AGREES THAT DUCKS UNLIMITED, INC. IS NOT RESPONSIBLE FOR THEIR USE OF THE MATERIAL, DATA AND INFORMATION OR THE RESULTS THEREOF.

1 L.S.

1 L.S.

1 L.S.

1 L.S.




PRIOR WRITTEN CONSENT OF AN AUTHORIZED AGENT OF DUCKS UNLIMITED, INC. DUCKS UNLIMITED, INC. MAKES NO REPRESENTATION OR WARRANTY OF ANY KIND

REGARDING THIS MATERIAL, DATA AND INFORMATION, INCLUDING, BUT NOT LIMITED TO, THE ACCURACY OF THE MATERIAL, DATA AND INFORMATION OR ITS SUITABILITY

USER AGREES THAT DUCKS UNLIMITED, INC. IS NOT RESPONSIBLE FOR THEIR USE OF THE MATERIAL, DATA AND INFORMATION OR THE RESULTS THEREOF.


FOR ANY PURPOSE. ALL USE OF THE MATERIAL, DATA AND INFORMATION IS AT THE USERS SOLE RISK. BY USING ANY OF THIS MATERIAL, DATA AND INFORMATION,

BEFORE THE START OF CONSTRUCTION. THE OWNER OF ANY UTILITIES INVOLVED MUST BE NOTIFIED. THE EXCAVATOR/CONTRACTOR IS RESPONSIBLE FOR GIVING THIS NOTICE BY CALLING "ONE CALL OF WYOMING" AT 811. A 72 HOUR NOTIFICATION AND FULL DESCRIPTION OF LOCATION IS REQUIRED



Dirt Balance			
Location	Cut (CY)	Fill (CY)	
Regrade Headgate	1383	1383	
Grade In Settling Basin	520		
Cleanout & Regrade Coot Ditch	710		
Temporary Road Construction		≃ 1000	
Reinforce Headgate Area		230	
Total	2613	2613	

HORIZONTAL AND VERTICAL CONTROL OPUS SOLUTION - COORDINATES ARE UTM ZONE 12 GRID COORDINATES IN US FEET [NAD83]. THEY WERE ESTABLISHED FROM THE WGS84 ELLIPSOID WITH INFORMATION FROM A TRIMBLE R10 SURVEY GRADE GPS RECEIVER ON NOVEMBER 10, 2022 AT DUCKS UNLIMITED CONTROL POINT DU-156-2022 AND CALIBRATED TO AN OPUS POSITION OCCUPIED FOR 3 HOURS AND 27 MINUTES AND SENT TO NGS FOR SOLUTION. THE VERTICAL CONTROL CAME FROM THE SAME SOLUTION USING GEOID 18 CONUS IN THE NAVD88. THE FULL OPUS SOLUTION REPORT IS ON FILE AT THE DUCKS UNLIMITED ENGINEERING DEPARTMENT IN FORT COLLINS, COLORADO.



EXISTING CULVERT

TEMPORARY ROAD

EXAMPLE OF DUCKS UNLIMITED **CONTROL POINT SURVEY CAP**

ABBREVIATIONS LIST

O.C. = ON CENTER

BLDC = BUILDING CORNER BRK = BREAKBTM. = BOTTOMC.L. = CENTER LINECMP = CORRUGATED METAL PIPE ROUND P.T. = POINT OF TANGENCY CMPA = CORRUGATED METAL PIPE ARCH RCP = REINFORCED CONCRETE PIPE CONC. = CONCRETE DIA. = DIAMETER E = EASTING COORDINATE OR EASTELEV. = ELEVATIONEMB. = EMBANKMENT EPAV = EDGE OF PAVEMENT EX. = EXISTINGEXIST. = EXISTINGFES = FLARED END SECTION FSL = FULL SERVICE LEVEL GA. = GAUGEG.W. = GUY WIREINV = INVERTLAT = LATITUDE (WGS84)LONG = LONGITUDE (WGS84)L.F. = LINEAR FEET MISC = MISCELLANEOUS N = NORTHING COORDINATE OR NORTHNFES = NON-FLARED END SECTION

O.C.E.W. = ON CENTER EACH WAY OHE = OVERHEAD ELECTRIC P.C. = POINT OF INTERSECTION P.I. = POINT OF INTERSECTION RD = ROAD

REM. = REMOVE REQ'D = REQUIREDR.O.W. = RIGHT OF WAYS = SOUTHSED. = SEDIMENT SHLD = SHOULDERSLP = SLOPESTPLG = STOPLOGTBM = TEMPORARY BENCHMARK

TEL = TELEPHONE/COMMUNICATOINS UG = UNDERGROUND VEG = VEGETATION W = WEST OR WITH

WCS = WATER CONTROL STRUCTURE WL = WATER LEVEL WS = WATER SHOT


*NOTE: NOT ALL ABBREVIATIONS IN THIS LIST APPEAR ON THIS SHEET

DU PROJECT ENGINEER: THOMAS PARKER, P.E. (970) 692-3375

UNLIMITED

GREAT PLAINS REGIONAL OFFICE P.E. SEAL:







04/16/2025 SHEET TITLE: OVERALL PLAN


SCALES ARE ACCURATE ON 24"X36" SHEET SIZE

DU PROJECT NUMBER: WY - 178 - 1

SHEET NUMBER: SHEET 2 OF 20







THIS MATERIAL, DATA AND INFORMATION IS THE PROPERTY OF DUCKS UNLIMITED, INC. IT MAY NOT BE USED OR REPRODUCED FOR ANY PURPOSE WITHOUT THE PRIOR WRITTEN CONSENT OF AN AUTHORIZED AGENT OF DUCKS UNLIMITED, INC. DUCKS UNLIMITED, INC. MAKES NO REPRESENTATION OR WARRANTY OF ANY KIND REGARDING THIS MATERIAL, DATA AND INFORMATION, INCLUDING, BUT NOT LIMITED TO, THE ACCURACY OF THE MATERIAL, DATA AND INFORMATION OR ITS SUITABILITY FOR ANY PURPOSE. ALL USE OF THE MATERIAL, DATA AND INFORMATION, USER AGREES THAT DUCKS UNLIMITED, INC. IS NOT RESPONSIBLE FOR THEIR USE OF THE MATERIAL, DATA AND INFORMATION OR THE RESULTS THEREOF.

BEFORE THE START OF CONSTRUCTION. THE OWNER OF ANY UTILITIES INVOLVED MUST BE NOTIFIED. THE EXCAVATOR/CONTRACTOR IS RESPONSIBLE FOR GIVING THIS NOTICE BY CALLING "ONE CALL OF WYOMING" AT 811.

A 72 HOUR NOTIFICATION AND FULL DESCRIPTION OF LOCATION IS REQUIRED.

"BEFORE YOU DIG"

BY ASTM D-4253.

EACH LAYER SHALL BE COMPACTED BY SURFACE OR INTERNAL VIBRATORS, HAND OR POWER TAMPERS OR OTHER SUITABLE COMPACTION EQUIPMENT. THE MATERIAL SHALL HAVE A MINIMUM COMPACTION OF 70% RELATIVE DENSITY AS DETEREMINED

DU PROJECT ENGINEER: THOMAS PARKER, P.E. (970) 692-3375

UNLIMITED GREAT PLAINS REGIONAL OFFICE - 2 N 4 G 0 V 8 ET ALP FLUSHIN

> DATE: 04/16/2025 SHEET TITLE:


FLUSHING
CULVERT SCREW
GATE


SCALES ARE ACCURATE ON 24"X36" SHEET SIZE


DU PROJECT NUMBER: WY-178-1


SHEET NUMBER:

SHEET 4 OF 20









PIPE BEDDING NOTES:

1. THERE SHALL BE A MINIMUM OF 12" OF BACKFILL OVER THE PIPE BEFORE OTHER THAN HAND COMPACTION EQUIPMENT IS USED IN THE TRENCH.

2. THE BEDDING MATERIAL SHALL BE CLEAN, FREE DRAINING WELL-GRADED SAND AND SHALL CONFORM TO THE LIMITS DEFINED IN THE CONSTRUCTION SPECIFICATIONS WHEN TESTED BY MEANS OF LABORATORY SIEVES.

3. BEDDING SHALL BE DEPOSITED IN LAYERS NOT EXCEEDING SIX (6) INCHES. EACH LAYER SHALL BE COMPACTED BY SURFACE OR INTERNAL VIBRATORS, HAND OR POWER TAMPERS OR OTHER SUITABLE COMPACTION EQUIPMENT. THE MATERIAL SHALL HAVE A MINIMUM COMPACTION OF 70% RELATIVE DENSITY AS DETEREMINED BY ASTM D-4253.

THIS MATERIAL, DATA AND INFORMATION IS THE PROPERTY OF DUCKS UNLIMITED, INC. IT MAY NOT BE USED OR REPRODUCED FOR ANY PURPOSE WITHOUT THE PRIOR WRITTEN CONSENT OF AN AUTHORIZED AGENT OF DUCKS UNLIMITED, INC. DUCKS UNLIMITED, INC. MAKES NO REPRESENTATION OR WARRANTY OF ANY KIND REGARDING THIS MATERIAL, DATA AND INFORMATION, INCLUDING, BUT NOT LIMITED TO, THE ACCURACY OF THE MATERIAL, DATA AND INFORMATION OR ITS SUITABILITY FOR ANY PURPOSE. ALL USE OF THE MATERIAL, DATA AND INFORMATION, USER AGREES THAT DUCKS UNLIMITED, INC. IS NOT RESPONSIBLE FOR THEIR USE OF THE MATERIAL, DATA AND INFORMATION OR THE RESULTS THEREOF.

"BEFORE YOU DIG"
BEFORE THE START OF CONSTRUCTION. THE OWNER OF ANY UTILITIES
INVOLVED MUST BE NOTIFIED. THE EXCAVATOR/CONTRACTOR IS RESPONSIBLE
FOR GIVING THIS NOTICE BY CALLING "ONE CALL OF WYOMING" AT 811.
A 72 HOUR NOTIFICATION AND FULL DESCRIPTION OF LOCATION IS REQUIRED

DU PROJECT ENGINEER: THOMAS PARKER, P.E. (970) 692-3375

REINFORCED CONCRETE PIPE

REPLACE CULVERT

RIPRAP

UNLIMITED GREAT PLAINS REGIONAL OFFICE P.E. SEAL: 》 15300分 - 2 N 4 U 9 N 8 \mathcal{O} ETLA ALP 04/16/2025 SHEET TITLE: MAIN SCREW GATE

SCALES ARE ACCURATE ON


WY - 178 - 1


SHEET 6 OF 20


24"X36" SHEET SIZE

DU PROJECT NUMBER:

SHEET NUMBER:









A 72 HOUR NOTIFICATION AND FULL DESCRIPTION OF LOCATION IS REQUIRED.

WY - 178 - 1SHEET NUMBER: SHEET 9 OF 20



TEMPORARY ROAD CONSTRUCTION NOTES:

- FILL SHALL BE OBTAINED FROM ACCEPTABLE CUT FROM COOT DITCH CLEAN-OUT, FROM SETTLING BASIN GRADING
- OR FROM LOCATION AS DESIGNATED BY DU CONSTRUCTION ENGINEER. FILL SHALL BE PLACED IN LIFTS NO MORE THAN 8" AND COMPACTED PRIOR TO PLACING SUBSEQUENT LIFTS.
- CONSTRUCTION OF TEMPORARY ROAD IS CONSIDERED PART OF BID ITEM "SITE PREPARATION".



TEMPORARY ROAD CONSTRUCTION SECTION SCALE 1" = 5'

THIS MATERIAL, DATA AND INFORMATION IS THE PROPERTY OF DUCKS UNLIMITED, INC. IT MAY NOT BE USED OR REPRODUCED FOR ANY PURPOSE WITHOUT THE PRIOR WRITTEN CONSENT OF AN AUTHORIZED AGENT OF DUCKS UNLIMITED, INC. DUCKS UNLIMITED, INC. MAKES NO REPRESENTATION OR WARRANTY OF ANY KIND REGARDING THIS MATERIAL, DATA AND INFORMATION, INCLUDING, BUT NOT LIMITED TO, THE ACCURACY OF THE MATERIAL, DATA AND INFORMATION OR ITS SUITABILITY FOR ANY PURPOSE. ALL USE OF THE MATERIAL, DATA AND INFORMATION IS AT THE USERS SOLE RISK. BY USING ANY OF THIS MATERIAL, DATA AND INFORMATION, USER AGREES THAT DUCKS UNLIMITED, INC. IS NOT RESPONSIBLE FOR THEIR USE OF THE MATERIAL, DATA AND INFORMATION OR THE RESULTS THEREOF.

"BEFORE YOU DIG" BEFORE THE START OF CONSTRUCTION. THE OWNER OF ANY UTILITIES INVOLVED MUST BE NOTIFIED. THE EXCAVATOR/CONTRACTOR IS RESPONSIBLE FOR GIVING THIS NOTICE BY CALLING "ONE CALL OF WYOMING" AT 811. A 72 HOUR NOTIFICATION AND FULL DESCRIPTION OF LOCATION IS REQUIRED.

DU PROJECT ENGINEER: THOMAS PARKER, P.E. (970) 692-3375

CONSTRUCT \mathcal{O} WETLAND TEMPORARY


04/16/2025 SHEET TITLE:


TEMPORARY ROAD CONSTRUCTION

SCALES ARE ACCURATE ON 24"X36" SHEET SIZE DU PROJECT NUMBER:

WY - 178 - 1SHEET NUMBER:

SHEET 10 OF 20





- Assembly: The structure shall be assembled in accordance with the Contech shop drawings and plate layout provided by Contech. Bolts shall be tightened to an applied torque between 100 and 150 ft-lbs.
- 2. Installation: The structure shall be installed in accordance with AASHTO Standard Specifications for Highway Bridges Section 26 or ASTM A807, the plans and specifications, and Contech's recommendations.
- The Contractor shall provide proper bedding and backfill to avoid distortion that may create undesirable stresses in the structure and/or settlement of the roadway. The bedding shall be free of rock formations,
- Backfill: The structure shall be backfilled using clean, well graded granular materials that meets the requirements of AASHTO M145 soil classifications A-1, A-2 or A-3. Aluminum box culverts shall be
- Backfill materials shall be placed in symmetrical lifts on each side of the structure. The differential between the lifts on either side shall not exceed 24 inches. Each layer of soil shall be placed in 6 to 8 inch loose lifts and compacted to a minimum of 90% density per AASHTO T99 or ASTM D698 (Standard Proctor). Aluminum box culverts shall be compacted to 90% density per AASHTO T180 or ASTM D1557 (Modified
- Backfill soils shall be free of rocks exceeding 3 inches, frozen lumps, ice, organic matter and foreign materials that could cause hard spots or decompose to create voids.
- granular material in the critical backfill zone or the use of non-woven geotextile to prevent soil migration.
- During backfilling operations, only small tracked construction equipment (such as a D-4 dozer or smaller) shall be near the structure as fill progresses above the crown and to the minimum height of cover. After adequate cover and compaction is achieved, live loads may increase at the direction of the Engineer.
- Critical Backfill Zone: The Engineer shall determine the extents of the critical backfill zone and provide a

SCALES ARE ACCURATE ON 24"X36" SHEET SIZE DU PROJECT NUMBER: WY - 178 - 1SHEET NUMBER: SHEET 11 OF 20

NDS

WETLA

INE

04/16/2025


ROAD CULVERT REPLACEMENT


SHEET TITLE:

ROAD

UÑĻĬŇİŤĔD

DU PROJECT ENGINEER: THOMAS PARKER, P.E. (970) 692-3375





LEGEND

PROPERTY BOUNDARY

EARTHWORK

CONCRETE HEADWALL/ TAILWALL

DU PROJECT ENGINEER:

THOMAS PARKER, P.E.

(970) 692-3375

SCREW GATE

REINFORCED CONCRETE PIPE

REPLACE CULVERT

RIPRAP

TEMPORARY ROAD

SHEET TITLE: CONTECH ||CULVERT DESIGN SHEETS 1-2

04/16/2025

Z

 Ξ

UNLIMITED INC.

SCALES ARE ACCURATE ON | 24"X36" SHEET SIZE

> DU PROJECT NUMBER: WY - 178 - 1

SHEET NUMBER: SHEET11A OF 20

D2 of D10


ALBC ALUMINUM BOX CULVERT 16'-10" SPAN X 8'-3" RISE


THIS MATERIAL, DATA AND INFORMATION IS THE PROPERTY OF DUCKS UNLIMITED, INC. IT MAY NOT BE USED OR REPRODUCED FOR ANY PURPOSE WITHOUT THE PRIOR WRITTEN CONSENT OF AN AUTHORIZED AGENT OF DUCKS UNLIMITED, INC. DUCKS UNLIMITED, INC. MAKES NO REPRESENTATION OR WARRANTY OF ANY KIND REGARDING THIS MATERIAL, DATA AND INFORMATION, INCLUDING, BUT NOT LIMITED TO, THE ACCURACY OF THE MATERIAL, DATA AND INFORMATION OR ITS SUITABILITY FOR ANY PURPOSE. ALL USE OF THE MATERIAL, DATA AND INFORMATION IS AT THE USERS SOLE RISK. BY USING ANY OF THIS MATERIAL, DATA AND INFORMATION, USER AGREES THAT DUCKS UNLIMITED, INC. IS NOT RESPONSIBLE FOR THEIR USE OF THE MATERIAL, DATA AND INFORMATION OR THE RESULTS THEREOF.


REVISION DESCRIPTION

800-338-1122 513-645-7000 513-645-7993 FAX

"BEFORE YOU DIG" BEFORE THE START OF CONSTRUCTION. THE OWNER OF ANY UTILITIES INVOLVED MUST BE NOTIFIED. THE EXCAVATOR/CONTRACTOR IS RESPONSIBLE FOR GIVING THIS NOTICE BY CALLING "ONE CALL OF WYOMING" AT 811. A 72 HOUR NOTIFICATION AND FULL DESCRIPTION OF LOCATION IS REQUIRED







LEGEND

PROPERTY BOUNDARY

EARTHWORK

CONCRETE HEADWALL/

TAILWALL

SCREW GATE

REINFORCED CONCRETE PIPE

REPLACE CULVERT

RIPRAP

TEMPORARY ROAD

DU PROJECT ENGINEER:

THOMAS PARKER, P.E.

(970) 692-3375

04/16/2025

ETLA

ALP

SHEET TITLE: CONTECH CULVERT DESIGN SHEETS 3-4

SCALES ARE ACCURATE ON 24"X36" SHEET SIZE


DU PROJECT NUMBER: WY - 178 - 1


SHEET NUMBER: SHEET11B OF 20


"BEFORE YOU DIG"

BEFORE THE START OF CONSTRUCTION. THE OWNER OF ANY UTILITIES INVOLVED MUST BE NOTIFIED. THE EXCAVATOR/CONTRACTOR IS RESPONSIBLE FOR GIVING THIS NOTICE BY CALLING "ONE CALL OF WYOMING" AT 811. A 72 HOUR NOTIFICATION AND FULL DESCRIPTION OF LOCATION IS REQUIRED.

THIS MATERIAL, DATA AND INFORMATION IS THE PROPERTY OF DUCKS UNLIMITED, INC. IT MAY NOT BE USED OR REPRODUCED FOR ANY PURPOSE WITHOUT THE PRIOR WRITTEN CONSENT OF AN AUTHORIZED AGENT OF DUCKS UNLIMITED, INC. DUCKS UNLIMITED, INC. MAKES NO REPRESENTATION OR WARRANTY OF ANY KIND REGARDING THIS MATERIAL, DATA AND INFORMATION, INCLUDING, BUT NOT LIMITED TO, THE ACCURACY OF THE MATERIAL, DATA AND INFORMATION OR ITS SUITABILITY FOR ANY PURPOSE. ALL USE OF THE MATERIAL, DATA AND INFORMATION IS AT THE USERS SOLE RISK. BY USING ANY OF THIS MATERIAL, DATA AND INFORMATION, USER AGREES THAT DUCKS UNLIMITED, INC. IS NOT RESPONSIBLE FOR THEIR USE OF THE MATERIAL, DATA AND INFORMATION OR THE RESULTS THEREOF.







LEGEND

PROPERTY BOUNDARY

EARTHWORK

CONCRETE HEADWALL/ **TAILWALL**

SCREW GATE

RIPRAP

REPLACE CULVERT

REINFORCED CONCRETE PIPE

DU PROJECT ENGINEER:

THOMAS PARKER, P.E.

(970) 692-3375

TEMPORARY ROAD

04/16/2025

TLA

 \bowtie

ALP

DESIGN

CONTECH

SHEET TITLE: CONTECH CULVERT DESIGN SHEETS 5-6

SCALES ARE ACCURATE ON 24"X36" SHEET SIZE


DU PROJECT NUMBER: WY - 178 - 1


SHEET NUMBER: SHEET11C OF 20


"BEFORE YOU DIG" BEFORE THE START OF CONSTRUCTION. THE OWNER OF ANY UTILITIES FOR GIVING THIS NOTICE BY CALLING "ONE CALL OF WYOMING" AT 811.

THIS MATERIAL, DATA AND INFORMATION IS THE PROPERTY OF DUCKS UNLIMITED, INC. IT MAY NOT BE USED OR REPRODUCED FOR ANY PURPOSE WITHOUT THE PRIOR WRITTEN CONSENT OF AN AUTHORIZED AGENT OF DUCKS UNLIMITED, INC. DUCKS UNLIMITED, INC. MAKES NO REPRESENTATION OR WARRANTY OF ANY KIND REGARDING THIS MATERIAL, DATA AND INFORMATION, INCLUDING, BUT NOT LIMITED TO, THE ACCURACY OF THE MATERIAL, DATA AND INFORMATION OR ITS SUITABILITY FOR ANY PURPOSE. ALL USE OF THE MATERIAL, DATA AND INFORMATION IS AT THE USERS SOLE RISK. BY USING ANY OF THIS MATERIAL, DATA AND INFORMATION, USER AGREES THAT DUCKS UNLIMITED, INC. IS NOT RESPONSIBLE FOR THEIR USE OF THE MATERIAL, DATA AND INFORMATION OR THE RESULTS THEREOF.

INVOLVED MUST BE NOTIFIED. THE EXCAVATOR/CONTRACTOR IS RESPONSIBLE A 72 HOUR NOTIFICATION AND FULL DESCRIPTION OF LOCATION IS REQUIRED.







LEGEND

PROPERTY BOUNDARY

EARTHWORK

CONCRETE HEADWALL/ TAILWALL

SCREW GATE

RIPRAP

REINFORCED CONCRETE PIPE

REPLACE CULVERT

DU PROJECT ENGINEER:

THOMAS PARKER, P.E.

(970) 692-3375

TEMPORARY ROAD

SHEET TITLE: CONTECH CULVERT DESIGN SHEETS 7-8

04/16/2025

 \blacksquare

 \vdash

 $\mathbf{\Omega}$

Z

 Ξ

UNLIMITED

INC.

SCALES ARE ACCURATE ON 24"X36" SHEET SIZE


DU PROJECT NUMBER: WY - 178 - 1


SHEET NUMBER SHEET11D OF 20


BEFORE YOU DIG" BEFORE THE START OF CONSTRUCTION. THE OWNER OF ANY UTILITIES INVOLVED MUST BE NOTIFIED. THE EXCAVATOR/CONTRACTOR IS RESPONSIBLE

A 72 HOUR NOTIFICATION AND FULL DESCRIPTION OF LOCATION IS REQUIRED

FOR GIVING THIS NOTICE BY CALLING "ONE CALL OF WYOMING" AT 811.







LEGEND

PROPERTY BOUNDARY

EARTHWORK

CONCRETE HEADWALL/ **TAILWALL**

SCREW GATE

REINFORCED CONCRETE PIPE

REPLACE CULVERT

RIPRAP

DU PROJECT ENGINEER:

THOMAS PARKER, P.E.

(970) 692-3375

TEMPORARY ROAD

SCALES ARE ACCURATE ON

SHEETS 9-10

04/16/2025

SHEET TITLE: ||CONTECH

CULVERT

DESIGN

TLA

 \blacksquare

ALP


Z


24"X36" SHEET SIZE DU PROJECT NUMBER: WY - 178 - 1

SHEET NUMBER: SHEET11E OF 20


THIS MATERIAL, DATA AND INFORMATION IS THE PROPERTY OF DUCKS UNLIMITED, INC. IT MAY NOT BE USED OR REPRODUCED FOR ANY PURPOSE WITHOUT THE PRIOR WRITTEN CONSENT OF AN AUTHORIZED AGENT OF DUCKS UNLIMITED, INC. DUCKS UNLIMITED, INC. MAKES NO REPRESENTATION OR WARRANTY OF ANY KIND REGARDING THIS MATERIAL, DATA AND INFORMATION, INCLUDING, BUT NOT LIMITED TO, THE ACCURACY OF THE MATERIAL, DATA AND INFORMATION OR ITS SUITABILITY FOR ANY PURPOSE. ALL USE OF THE MATERIAL, DATA AND INFORMATION IS AT THE USERS SOLE RISK. BY USING ANY OF THIS MATERIAL, DATA AND INFORMATION, USER AGREES THAT DUCKS UNLIMITED, INC. IS NOT RESPONSIBLE FOR THEIR USE OF THE MATERIAL, DATA AND INFORMATION OR THE RESULTS THEREOF.

"BEFORE YOU DIG" BEFORE THE START OF CONSTRUCTION. THE OWNER OF ANY UTILITIES INVOLVED MUST BE NOTIFIED. THE EXCAVATOR/CONTRACTOR IS RESPONSIBLE FOR GIVING THIS NOTICE BY CALLING "ONE CALL OF WYOMING" AT 811. A 72 HOUR NOTIFICATION AND FULL DESCRIPTION OF LOCATION IS REQUIRED.





ARMORED SPILLWAY SECTION CUT (RUDDY DUCK RESERVOIR) SCALE 1"=5'



ARMORED SPILLWAY PROFILE VIEW (RUDDY DUCK RESERVOIR)

SCALE 1"=5"

THIS MATERIAL, DATA AND INFORMATION IS THE PROPERTY OF DUCKS UNLIMITED, INC. IT MAY NOT BE USED OR REPRODUCED FOR ANY PURPOSE WITHOUT THE PRIOR WRITTEN CONSENT OF AN AUTHORIZED AGENT OF DUCKS UNLIMITED, INC. DUCKS UNLIMITED, INC. MAKES NO REPRESENTATION OR WARRANTY OF ANY KIND REGARDING THIS MATERIAL, DATA AND INFORMATION, INCLUDING, BUT NOT LIMITED TO, THE ACCURACY OF THE MATERIAL, DATA AND INFORMATION OR ITS SUITABILITY FOR ANY PURPOSE. ALL USE OF THE MATERIAL, DATA AND INFORMATION, USER AGREES THAT DUCKS UNLIMITED, INC. IS NOT RESPONSIBLE FOR THEIR USE OF THE MATERIAL, DATA AND INFORMATION OR THE RESULTS THEREOF.

"BEFORE YOU DIG"

BEFORE THE START OF CONSTRUCTION. THE OWNER OF ANY UTILITIES INVOLVED MUST BE NOTIFIED. THE EXCAVATOR/CONTRACTOR IS RESPONSIBLE FOR GIVING THIS NOTICE BY CALLING "ONE CALL OF WYOMING" AT 811.


A 72 HOUR NOTIFICATION AND FULL DESCRIPTION OF LOCATION IS REQUIRED.

DU PROJECT ENGINEER: THOMAS PARKER, P.E. (970) 692-3375 DUCKS UNLIMITED INC.

P.E. SEAL:

| SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: | SEAL: |

DESIGNED BY: KJW
DRAWN BY: JJW
SURVEYED BY: TP
CHECKED BY:
APPROVED BY:
APPROVED BY:



ALPINE WETLANDS
RUDDY DUCK RESERVOIR
ARMORED SPILLWAY

SHEET TITLE:

DATE:
04/16/2025
SHEET TITLE:
RUDDY DUCK

RUDDY DUCK
RESERVOIR
ARMORED
SPILLWAY


SCALES ARE ACCURATE ON 24"X36" SHEET SIZE

DU PROJECT NUMBER: WY-178-1

SHEET NUMBER:

1 2

SHEET 12 OF 20



THIS MATERIAL, DATA AND INFORMATION IS THE PROPERTY OF DUCKS UNLIMITED, INC. IT MAY NOT BE USED OR REPRODUCED FOR ANY PURPOSE WITHOUT THE PRIOR WRITTEN CONSENT OF AN AUTHORIZED AGENT OF DUCKS UNLIMITED, INC. DUCKS UNLIMITED, INC. MAKES NO REPRESENTATION OR WARRANTY OF ANY KIND REGARDING THIS MATERIAL, DATA AND INFORMATION, INCLUDING, BUT NOT LIMITED TO, THE ACCURACY OF THE MATERIAL, DATA AND INFORMATION OR ITS SUITABILITY FOR ANY PURPOSE. ALL USE OF THE MATERIAL, DATA AND INFORMATION IS AT THE USERS SOLE RISK. BY USING ANY OF THIS MATERIAL, DATA AND INFORMATION, USER AGREES THAT DUCKS UNLIMITED, INC. IS NOT RESPONSIBLE FOR THEIR USE OF THE MATERIAL, DATA AND INFORMATION OR THE RESULTS THEREOF.

FLOW -

10 CUBIC YARDS OF DU-

CLASS II ROCK RIPRAP WITH, FILTER FABRIC BENEATH.

PINTAIL RESERVOIR

SPILLWAY INVERT ELEV. = 5,623.0

10 CUBIC YARDS OF DU CLASS II ROCK RIPRAP WITH FILTER FABRIC BENEATH.

FLOW -

(INVERT WIDTH)

ARMORED SPILLWAY SECTION CUT (PINTAIL RESERVOIR)

SCALE 1"=5'

11' TOP WIDTH

ARMORED SPILLWAY PROFILE VIEW (PINTAIL RESERVOIR)

SCALE 1"=5'

ELEV. = 5,625.0

SPILLWAY

CHANNEL

"BEFORE YOU DIG" BEFORE THE START OF CONSTRUCTION. THE OWNER OF ANY UTILITIES INVOLVED MUST BE NOTIFIED. THE EXCAVATOR/CONTRACTOR IS RESPONSIBLE FOR GIVING THIS NOTICE BY CALLING "ONE CALL OF WYOMING" AT 811. A 72 HOUR NOTIFICATION AND FULL DESCRIPTION OF LOCATION IS REQUIRED.


DU PROJECT ENGINEER: THOMAS PARKER, P.E. (970) 692-3375


SCALES ARE ACCURATE ON 24"X36" SHEET SIZE DU PROJECT NUMBER: WY - 178 - 1SHEET NUMBER:

HECK

ARMORED SPILLWAY & ROCK


19 SHEET 13 OF 20





ARMORED SPILLWAY SECTION CUT (TEAL RESERVOIR)

SCALE 1"=5"




THIS MATERIAL, DATA AND INFORMATION IS THE PROPERTY OF DUCKS UNLIMITED, INC. IT MAY NOT BE USED OR REPRODUCED FOR ANY PURPOSE WITHOUT THE PRIOR WRITTEN CONSENT OF AN AUTHORIZED AGENT OF DUCKS UNLIMITED, INC. DUCKS UNLIMITED, INC. MAKES NO REPRESENTATION OR WARRANTY OF ANY KIND REGARDING THIS MATERIAL, DATA AND INFORMATION, INCLUDING, BUT NOT LIMITED TO, THE ACCURACY OF THE MATERIAL, DATA AND INFORMATION OR ITS SUITABILITY FOR ANY PURPOSE. ALL USE OF THE MATERIAL, DATA AND INFORMATION, USER AGREES THAT DUCKS UNLIMITED, INC. IS NOT RESPONSIBLE FOR THEIR USE OF THE MATERIAL, DATA AND INFORMATION OR THE RESULTS THEREOF.


"BEFORE YOU DIG"
BEFORE THE START OF CONSTRUCTION. THE OWNER OF ANY UTILITIES
INVOLVED MUST BE NOTIFIED. THE EXCAVATOR/CONTRACTOR IS RESPONSIBLE
FOR GIVING THIS NOTICE BY CALLING "ONE CALL OF WYOMING" AT 811.
A 72 HOUR NOTIFICATION AND FULL DESCRIPTION OF LOCATION IS REQUIRED.

DU PROJECT ENGINEER: THOMAS PARKER, P.E. (970) 692-3375





DESIGNED BY: KJW DRAWN BY: JJW	SURVEYED BY: TP	CHECKED BY:	APPROVED BY:	APPROVED RY:
--------------------------------	-----------------	-------------	--------------	--------------



ALPINE WETLANDS TEAL RESERVOIR ARMORED SPILLWAY

SHEFT TITLE:

DATE:
04/16/2025

SHEET TITLE:
TEAL
RESERVOIR
ARMORED
SPILLWAY

SCALES ARE ACCURATE ON 24"X36" SHEET SIZE


DU PROJECT NUMBER:


DU PROJECT NUMBER: WY-178-1


SHEET NUMBER:

1


SHEET 14 OF 20







AMORED SPILLWAY SECTION CUT (MERGANSER RESERVOIR) SCALE 1"=5'



THIS MATERIAL, DATA AND INFORMATION IS THE PROPERTY OF DUCKS UNLIMITED, INC. IT MAY NOT BE USED OR REPRODUCED FOR ANY PURPOSE WITHOUT THE PRIOR WRITTEN CONSENT OF AN AUTHORIZED AGENT OF DUCKS UNLIMITED, INC. DUCKS UNLIMITED, INC. MAKES NO REPRESENTATION OR WARRANTY OF ANY KIND REGARDING THIS MATERIAL, DATA AND INFORMATION, INCLUDING, BUT NOT LIMITED TO, THE ACCURACY OF THE MATERIAL, DATA AND INFORMATION OR ITS SUITABILITY FOR ANY PURPOSE. ALL USE OF THE MATERIAL, DATA AND INFORMATION IS AT THE USERS SOLE RISK. BY USING ANY OF THIS MATERIAL, DATA AND INFORMATION, USER AGREES THAT DUCKS UNLIMITED, INC. IS NOT RESPONSIBLE FOR THEIR USE OF THE MATERIAL, DATA AND INFORMATION OR THE RESULTS THEREOF.

"BEFORE YOU DIG"

BEFORE THE START OF CONSTRUCTION. THE OWNER OF ANY UTILITIES INVOLVED MUST BE NOTIFIED. THE EXCAVATOR/CONTRACTOR IS RESPONSIBLE FOR GIVING THIS NOTICE BY CALLING "ONE CALL OF WYOMING" AT 811. A 72 HOUR NOTIFICATION AND FULL DESCRIPTION OF LOCATION IS REQUIRED.

DU PROJECT ENGINEER: THOMAS PARKER, P.E. (970) 692-3375

INSTALLING ARMORED SPILLWAYS

ARMORED SPILLWAY SCALES ARE ACCURATE ON

04/16/2025

MERGANSER RESERVOIR

SHEET TITLE:

DUCKS UNLIMITED INC.

GREAT PLAINS REGIONAL OFFICE

- 0 W 4 W 0 V 8

RESERVOIR SPILLWAY

MERGANSER ARMORED


WETLAND


ALPIN]


P.E. SEAL:

24"X36" SHEET SIZE DU PROJECT NUMBER: WY - 178 - 1

SHEET NUMBER: 15 SHEET 15 OF 20







USER AGREES THAT DUCKS UNLIMITED, INC. IS NOT RESPONSIBLE FOR THEIR USE OF THE MATERIAL, DATA AND INFORMATION OR THE RESULTS THEREOF.

FOR GIVING THIS NOTICE BY CALLING "ONE CALL OF WYOMING" AT 811. A 72 HOUR NOTIFICATION AND FULL DESCRIPTION OF LOCATION IS REQUIRED. LEGEND

PROPERTY BOUNDARY

REPLACE CULVERT

TEMPORARY ROAD

DUCKS UNLIMITED INC.

GREAT PLAINS REGIONAL OFFICE

- N W 4 W 0 V 8

 \mathcal{O} ETLA

 \bowtie

O.C.E.W. = ON CENTER EACH WAY OHE = OVERHEAD ELECTRIC
P.C. = POINT OF INTERSECTION

P.I. = POINT OF INTERSECTION

TBM = TEMPORARY BENCHMARK

TEL = TELEPHONE/COMMUNICATOINS

WCS = WATER CONTROL STRUCTURE

*NOTE: NOT ALL ABBREVIATIONS IN

THIS LIST APPEAR ON THIS SHEET

RD = ROAD

S = SOUTH

REM. = REMOVE

SED. = SEDIMENT

SLP = SLOPE

SHLD = SHOULDER

STPLG = STOPLOG

UG = UNDERGROUND

VEG = VEGETATION

W = WEST OR WITH

WL = WATER LEVEL

WS = WATER SHOT

DU PROJECT ENGINEER:

THOMAS PARKER, P.E.

(970) 692-3375

REQ'D = REQUIRED

R.O.W. = RIGHT OF WAY

CONTROL


04/16/2025

SHEET TITLE: TRAFFIC CONTROL PLAN

SCALES ARE ACCURATE ON 24"X36" SHEET SIZE

DU PROJECT NUMBER: WY - 178 - 1

SHEET NUMBER: SHEET 18 OF 20




REGARDING THIS MATERIAL, DATA AND INFORMATION, INCLUDING, BUT NOT LIMITED TO, THE ACCURACY OF THE MATERIAL, DATA AND INFORMATION OR ITS SUITABILITY FOR ANY PURPOSE. ALL USE OF THE MATERIAL, DATA AND INFORMATION IS AT THE USERS SOLE RISK. BY USING ANY OF THIS MATERIAL, DATA AND INFORMATION, USER AGREES THAT DUCKS UNLIMITED, INC. IS NOT RESPONSIBLE FOR THEIR USE OF THE MATERIAL, DATA AND INFORMATION OR THE RESULTS THEREOF.

INVOLVED MUST BE NOTIFIED. THE EXCAVATOR/CONTRACTOR IS RESPONSIBLE FOR GIVING THIS NOTICE BY CALLING "ONE CALL OF WYOMING" AT 811. A 72 HOUR NOTIFICATION AND FULL DESCRIPTION OF LOCATION IS REQUIRED.

LEGEND

PROPERTY BOUNDARY

FULL SERVICE LEVEL (FSL



EARTHWORK



CONCRETE HEADWALL/ **TAILWALL**



SCREW GATE



REINFORCED CONCRETE PIPE



REPLACE CULVERT













ABBREVIATIONS LIST

BLDC = BUILDING CORNER BRK = BREAKBTM. = BOTTOMC.L. = CENTER LINE

CONC. = CONCRETEDIA. = DIAMETER E = EASTING COORDINATE OR EASTELEV. = ELEVATION

EPAV = EDGE OF PAVEMENT EX. = EXISTINGEXIST. = EXISTINGFES = FLARED END SECTION FSL = FULL SERVICE LEVEL GA. = GAUGE

G.W. = GUY WIREINV = INVERTLAT = LATITUDE (WGS84)LONG = LONGITUDE (WGS84)L.F. = LINEAR FEET MISC = MISCELLANEOUS

O.C. = ON CENTER

N = NORTHING COORDINATE OR NORTH NFES = NON-FLARED END SECTION

O.C.E.W. = ON CENTER EACH WAY OHE = OVERHEAD ELECTRIC P.C. = POINT OF INTERSECTION P.I. = POINT OF INTERSECTION

CMP = CORRUGATED METAL PIPE ROUND P.T. = POINT OF TANGENCY CMPA = CORRUGATED METAL PIPE ARCH RCP = REINFORCED CONCRETE PIPE RD = ROADREM. = REMOVEREQ'D = REQUIREDR.O.W. = RIGHT OF WAYS = SOUTH

SED. = SEDIMENT

SHLD = SHOULDERSLP = SLOPESTPLG = STOPLOGTBM = TEMPORARY BENCHMARK TEL = TELEPHONE/COMMUNICATOINS UG = UNDERGROUND


VEG = VEGETATION W = WEST OR WITHWCS = WATER CONTROL STRUCTURE WL = WATER LEVELWS = WATER SHOT

*NOTE: NOT ALL ABBREVIATIONS IN THIS LIST APPEAR ON THIS SHEET

DU PROJECT ENGINEER: THOMAS PARKER, P.E. (970) 692-3375



GREAT PLAINS REGIONAL OFFICE P.E. SEAL:



WETLAND

ORMWAT

04/16/2025 SHEET TITLE: STORMWATER

POLLUTION PREVENTION PLAN

SCALES ARE ACCURATE ON 24"X36" SHEET SIZE

DU PROJECT NUMBER: WY - 178 - 1SHEET NUMBER:

19 SHEET 19 OF 20

WYPDES Permit #)	G	ges are made to the construction project	
issued on/ shall apply for this project.	Temporary or Permanent Seeding Controls of	quire alterations in the temporary erosion the site, the Storm Water Pollution	
Tol this project.	• Plantina	Plan (SWPPP) will be amended to provide	
ABBREVIATIONS	 Mulching (Straw or Cellulose Fiber) 	protection to disturbed areas, all storm tures, and adjacent waters. The SWPPP will	
WDEQ: Wyoming Department of Environmental Quality WYPDES: Wyoming Pollution Discharge Elimination	• FIOSION CONTOL DIGHKEIS OF WILLS	in a designated place for review over the	
System	 Roughened Surface (e.g. tracking) 	the project.	
USFWS: United States Fish and Wildlife Service	 Gabions—Gabion Mattress X Other: Rip Rap 		
SWMP: Storm Water Management Plan			
LOCATION/NARRATIVE	Structural Temporary Erosion and Sediment Controls • Silt Fence		
Location: See Sheet 1 for the location of this	• Temporary Berm	DAILY STORMWATER F	POLLUTION PREVENTION PLAN LOG BOOK
project. Project Limits: See Sheet 2 of this plan for the	 Temporary Slope Drain Straw Wattles or Rolls		
project limits. This sheet covers the earthwork,	 Diversion Channels/Swales 	SWPPP ADMINISTRATOR:	
water control structures and rock riprap.	 Channel Liners (TRM) Stone Rip Rap Sheet	INSPECTOR:	DATE/TIME:
PROJECT CONTACTS	 X Rock Check Dams 		
SWPPP Administrator:	 Sediment Traps/Basins X Inlet Protection 	INSPECTION ITEMS:	
Thomas Parker, P.E. Ducks Unlimited	X Outlet Protection	• Inlet Filters	
Cell: 970-692-3375	 Surface Inlet Protection Curb Inlet Protection	• Straw Bale Dikes	
Email: tparker@ducks.org	 Stabilized Construction Entrances 	• Silt Fence	
The Contractor is responsible for implementation of the	• Other	• Pond Outlet	
SWPPP and installation, inspection and maintenance of	DESCRIPTION OF CONSTRUCTION ACTIVITIES	• Vehicle Tracking Pad	
the erosion prevention and sediment control BMP's before and during construction.	The proposed construction activities will provide water level management to the site. Through this	• Pond Sediment	
	management more desirable wetlands will be created.	• Surface Erosion	
Contractor Name: Company:		• Riprap Structures	
Telephone Number:	Major Soil Disturbing Activities (check all that apply): • _X_ Clearing & Grubbing	• Drainage Pans	
Email:	 X Creding & Grabbing X Grading & Shaping 		
SPILL NOTIFICATION	 X Cutting & Filling 	REPAIRS OR MAINTENANCE NEEDED:	
In the event of a spill, the contractor's site	• Other (describe):		
superintendent will make the appropriate notificiaton(s), consistent with the following procedures:	ORDER OF CONSTRUCTION ACTIVITIES		
1. A reportable spill is a quantity of 25 gallons of	(Stabilization measures shall be initiated as soon as possible,	REPAIRS OR MAINTENANCE MADE:	
petroleum which must be reported immediately to the DEQ Water Quality Division.	but in no case later than 14 days after the construction	THE AIRS OR WAINTENANCE WADE.	
2. Any spill of oil or hazardous substance to waters of	activity in that portion of the site has temporarily or permanently ceased.)		
the state must be reported immediately.	 Install initial erosion and sediment control measures. 		
Wyoming Department of Environmental Quality's Spill and Complaint:	 Proceed with site grading and construction activities. Stabilize areas disturbed by construction activities with 		
DEQSpills.wyo.gov —or— 24 Hour (307) 777—7781	temporary erosion and sediment control measures.	MAINTENANCE ITEMS:	
4. Within 7 days following a release, submit a written report to the DEQ Water Quality Division describing	 Install water control structure. 		
the reportable release, the response, and the steps	Complete final grading.Complete permanent erosion and sediment control		
taken to prevent recurrence.	measures.		
POTENTIAL POLLUTION SOURCES	ESTIMATED PROJECT AREA QUANTITIES	CONTACTS MADE:	_ AGENCY:
Heavy machinery will be operated on the project site	Total Project Area: 189 Acres		
requiring the use of fuel trucks. Contamination due to fuel spills and oil leaks is possible due to the	Total Area to Be Disturbed: 4.8 Acres Existing Impervious Area: 0.0 Acres	MATERIALS HANDLING:	
large volume of work being performed. Day to day	Proposed Impervious Area: 0.0 Acres	ITEMS DELIVERED:	
cleaning and maintenance of equipment has the	EXISTING GROUND COVER	A OTIONIC TALKENI	
potential to impact stormwater quality. Delivery of site materials also has potential for impacting runoff	Currently the site is mostly native grass and trees. There	ACTIONS TAKEN:	
quality. Another potential pollution source is sediment	are six existing wetlands on—site. Water is managed in	SPILL REPORTING:	
transport from earthwork.	the reservoirs using water control structures.	MATERIAL SPILLED:	
POLLUTION PREVENTION MANAGEMENT MEASURES	NON-STORMWATER DISCHARGE	WIATERIAL STILLED.	
• Solid Wastes (None anticipated):	None.	WHY MATERIAL SPILLED:	
Collected sediment, asphalt, and concrete millings, floating debris, paper, plastic, fabric, construction and	RECEIVING WATER		
demolition debris and other wastes must be disposed of	Runoff from the site is retained by the existing reservoir	QUANTITY:	
properly and must comply with the DEQ Water Quality Division disposal requirements.	outlet works. During a flooding event, water from the project area would ultimately drain into the Shoshone River.		
 Hazardous Materials (None anticipated): 		LOCATION:	
Oil, gasoline, paint and any hazardous substances	STREAM CROSSINGS LOCATED WITHIN THE CONSTRUCTION SITE BOUNDARY		
must be properly stored, including secondary containment, to prevent spills, leaks or other discharge.	None.	WEATHER CONDITIONS:	
Restricted access to storage areas must be provided to	LOCATION OF SWPPP REQUIREMENTS IN PROJECT PLAN		
prevent vandalism. Storage and disposal of hazardous waste must be in compliance with DEQ Water Quality	See the Erosion and Sediment Control notes and details	SPILL START TIME:	SPILL STOP TIME: AM/PM
Division regulations.	on the Stormwater Pollution Prevention Plan sheets.		
 Vehicle Washing: External washing of trucks and other construction 	FINAL STABILIZATION AND LONGTERM STORMWATER	CLEANUP METHOD:	
vehicles must be limited to a defined area of the	MANAGEMENT		
site. Runoff must be contained and waste properly	Following site construction, the goal is to achieve a	DICDOCAL METLLOD.	
disposed of. No engine degreasing is allowed on site.	stabilized cover condition to provide long—term stormwater protection. Stabilization is quantified by	DISPOSAL METHOD:	
• Concrete Washout Onsite (No concrete anticipated):	achieving uniform cover equal to 70% of the		
All liquid and solid wastes generated by concrete	pre-disturbance condition. The post-construction		

CONSTRUCTION CHANGES

"BEFORE YOU DIG"

ENTER N/A IF ITEM IS NOT APPLICABLE TO THE SITE SWPPP.

BEFORE THE START OF CONSTRUCTION. THE OWNER OF ANY UTILITIES INVOLVED MUST BE NOTIFIED. THE EXCAVATOR/CONTRACTOR IS RESPONSIBLE FOR GIVING THIS NOTICE BY CALLING "ONE CALL OF WYOMING" AT 811. A 72 HOUR NOTIFICATION AND FULL DESCRIPTION OF LOCATION IS REQUIRED. MAINTENANCE AND INSPECTION

- Maintenance and Inspection Practices Inspections will be conducted at least one time per week and after a storm event of 0.50 inches or
- All controls will be maintained in good working order. Necessary repairs will be initiated within 24 hours of the site inspection report or as soon as field conditions allow access.
- Where work has been suspended due to frozen ground conditions, the required inspections and maintenance must take place as soon as runoff occurs at the site or prior to resuming construction, whichever comes first.
- Where parts of the construction site have undergone final stabilization, but work remains on other parts of the site, inspections of the stabilized areas may be reduced to once per month.
- Silt fence will be inspected for depth of sediment and for tears in order to ensure the fabric is securely anchored. Sediment buildup will be removed from the silt fence when it reaches $\frac{1}{2}$ of the height of the silt fence. All silt fences must be repaired, replaced, or supplemented when they become nonfunctional or the sediment reaches ¼ of the height of the fence.
- Sediment basins and traps will be checked. Sediment will be removed when the depth reaches approximately 50 percent of the structure's capacity.
- Check dams will be inspected for stability. Sediment will be removed when the depth reaches $\frac{1}{2}$ the height of the dam.
- All seeded areas will be checked for bare spots, washouts, and vigorous growth free of significant weed infestations.
- Surface waters, including drainage ditches and conveyance systems, must be inspected for evidence of sediment being deposited by erosion.
- Construction site vehicle exit locations must be inspected for evidence of off-site sediment tracking onto paved surfaces. Tracked sediment must be removed from all off-site paved surfaces within 24 hours of discovery.
- Disturbed areas will be checked for stabilization. Stabilization measures shall be initiated as soon as construction activity in that portion of the site has temporarily or permanently ceased.
- The normal wetted perimeter of any temporary or permanent drainage ditch or swale that drains water from any portion of the construction site, or diverts water around the site, must be stabilized within 200 lineal feet from the property edge, or from the point of discharge into any surface water. Stabilization of the last 200 lineal feet must be completed within 24 hours after connection to a
- Stabilization of the remaining portions of any temporary or permanent ditches or swales must be completed within 14 days after connecting to a surface water and construction in that portion of the ditch has temporarily or permanently ceased.
- Temporary or permanent ditches or swales that are being used as a sediment containment system (with properly designed rock ditch checks, bio rolls, silt dikes, etc.) do not need to be stabilized. These areas must be stabilized within 24 hours after no longer being used as a sediment containment
- Pipe outlets must be provided with temporary or permanent energy dissipation within 24 hours after connection to a surface water.
- Discharge procedures for water control and dewatering operations will be inspected. If the water cannot be discharged to a sedimentation basin prior to entering the surface water, it must be treated with the appropriate BMPs, such that the discharge does not adversely affect the receiving water or downstream landowners.
- Inspection and maintenance reports will be completed for each site inspection, this form will also be used to document changes to the SWMP. The report shall include the date and amount of precipitation or snowmelt events that cause surface erosion. A copy of the completed inspection form will be filed with the SWMP documents.
- The Contractor's site superintendent is responsible for inspection. Maintenance and repair activities are the responsibility of the Contractor.

DU PROJECT ENGINEER:

THOMAS PARKER, P.E.

(970) 692-3375

 \square 04/16/2025 SHEET TITLE: SWPPP NOTES SCALES ARE ACCURATE ON) 24"X36" SHEET SIZE DU PROJECT NUMBER: WY - 178 - 1SHEET NUMBER:

SHEET 20 OF 20

UNLIMITED

INC.

GREAT PLAINS REGIONAL OFFICE

15300

- 0 W 4 D O V 8

 \mathcal{O}

P.E. SEAL:

THIS MATERIAL, DATA AND INFORMATION IS THE PROPERTY OF DUCKS UNLIMITED, INC. IT MAY NOT BE USED OR REPRODUCED FOR ANY PURPOSE WITHOUT THE PRIOR WRITTEN CONSENT OF AN AUTHORIZED AGENT OF DUCKS UNLIMITED, INC. DUCKS UNLIMITED, INC. MAKES NO REPRESENTATION OR WARRANTY OF ANY KIND REGARDING THIS MATERIAL, DATA AND INFORMATION, INCLUDING, BUT NOT LIMITED TO, THE ACCURACY OF THE MATERIAL, DATA AND INFORMATION OR ITS SUITABILITY FOR ANY PURPOSE. ALL USE OF THE MATERIAL, DATA AND INFORMATION IS AT THE USERS SOLE RISK. BY USING ANY OF THIS MATERIAL, DATA AND INFORMATION, USER AGREES THAT DUCKS UNLIMITED, INC. IS NOT RESPONSIBLE FOR THEIR USE OF THE MATERIAL, DATA AND INFORMATION OR THE RESULTS THEREOF.

vegetation.

condition of the site shall be that the majority of the

the seeding takes, this shall virtually eliminate erosion

from the site. Permanent seeding with mulching is

fences following establishment of permanent stable

disturbed area will be compacted soil and seeded. Once

installed as needed. Drainage ditches, pans, and culverts

shall be cleaned of debris and sediment. Repair eroded

sloped or drainage paths by backfilling. Remove all silt

EROSION AND SEDIMENT CONTROLS

(Check all that apply)

STORM WATER POLLUTION PREVENTION PLAN

facilities.

washout operation must be contained in a leak-proof

containment facility or impermeable liner. A compacted

clav liner that does not allow washout liquids to enter

ground water is considered an impermeable liner. The

liquid and solid wastes must not contact the ground,

washout operation or areas. Liquid and solid wastes

must be disposed of properly and in compliance with

installed adjacent to each washout facility to inform

concrete equipment operators to utilize the proper

DEQ Water Quality Division regulations. A sign must be

and there must not be runoff from the concrete